

Dhaka Water Supply and Sewerage Authority

Office of the Executive Engineer

Civil Maintenance Division

6th Floor, WASA Bhaban, Kawran Bazar

98, Kazi Nazrul Islam Avenue, Dhaka-1215

Name of work: Plastering & painting with ancillary maintenance works at Khilgaon-4 No. water pump staff quarter (unit: 102) compound, Dhaka WASA

Sl. No.	Group	Basic of Rates PWD-2022	Description of work	Unit	Quantity	Unit Rate	Amount (Tk)
1	2	3	4	5	6	7	8
1	Civil	16.11	Approved best quality and colour synthetic polyvinyl distemper delivered from authorized local agent of the manufacturer in a sealed container, applying to wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of interior sealer of specified brand on prepared surface; then applying 1 coat of interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of synthetic polyvinyl distemper spreading by brush/roller/spray & necessary scaffolding etc. up to desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	sqm	158.504	213.001	33,761.511
2	Civil	15.1.1	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity etc.	sqm	51.208	315.001	16,130.571
						Total (TK)	49,892.082
						Say Total (TK)	49,892

IN WORD: FORTY NINE THOUSAND EIGHT HUNDRED NINETY TWO TAKA ONLY

Rate
20.09.26
রাফেজ আহমেদ
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়ার্ড।

Signature
20.09.26
মুজিব সাহা
নির্বাহী প্রকৌশলী
সিএম বিভাগ
ঢাকা ওয়ার্ড।