

Price and Delivery Schedule for Goods (Form e-PG2-2A)

Price and Delivery Schedule for Goods

Item No.	Description of Item	Measurement Unit	Quantity	Point of Delivery	Delivery Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Supplying, fitting and fixing country made mirror polished homogeneous floor tiles complying BDS ISO 13006: 2015, water absorption $\leq$ 0.5%, modulus of rupture (MOR) $\geq$ 27 N/mm ² , irrespective of color &/or design, with 20 mm thick cement sand (F.M. 1:2) mortar (1:4) base and raking out the joints with white cement including cutting and laying the tiles in proper way and finishing with care etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) In ground floor. GP Mirror Polished (Double Charge) 600 mm x 600 mm floor tiles.	sqm	268.790	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	2152.001	Two Thousand One Hundred and Fifty-Two point Zero Zero One	578436.349	Five Lakh Seventy-Eight Thousand Four Hundred and Thirty-Six point Three Four Nine
2	Supplying, fitting and fixing country made glazed wall tiles complying BDS ISO 13006: 2015, irrespective of color &/or design, with 20	sqm	191.550	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	2000.001	Two Thousand point Zero Zero One	383100.192	Three Lakh Eighty-Three Thousand One Hundred point One Nine Two

[illegible]

This Price and Delivery Schedule for Goods (Form e-PG2-2A) is Electronically Signed by Mr. Md Islam on behalf of S.S. Enterprise

S.S. Enterprise**Price and Completion Schedule for Related Services (Form e- PG2-2B)****Price and Completion Schedule for Related Services**

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Picking-up of unserviceable patent stone/situ mosaic from floor and dado etc. and removal of debris to a safe distance.	sqm	268.790	saidabad water treatment plant, Dhalpur, Dhaka.	180	Local	38.001	Thirty-Eight point Zero Zero One	10214.289	Ten Thousand Two Hundred and Fourteen point Two Eight Nine
								Grand Total:	10214.289	Ten Thousand Two Hundred and Fourteen point Two Eight Nine

This Price and Completion Schedule for Related Services (Form e- PG2-2B) is Electronically Signed by Mr. Md Islam on behalf of S.S. Enterprise