

M/S. Al-Amin International

Bill of Quantities

Item No. 1	Group 2	Item Code (if any) 3	Description of Items of Works 4	Measurement Unit 5	Quantity 6	Unit Price In figures (BDT) 7	Unit Price In words (BDT) 8	Total Price in figures (BDT) 9	Total Price In words (BDT) 10
1	Civil	-	Fitting, Fixing & Supply of MS Pipe (Normal) 200mm dia 6mm thickness.	m	12.000	2500.000	Two Thousand Five Hundred	30000.000	Thirty Thousand
2	Civil	-	Fitting, Fixing & Supply of MS ? S? bend (Normal) 200 mm dia (5'-6" long).	Each	4.000	9000.000	Nine Thousand	36000.000	Thirty-Six Thousand
3	Civil	-	Fitting, Fixing & Supply of M.S TEE 225X150X225 mm.	Each	4.000	6000.000	Six Thousand	24000.000	Twenty-Four Thousand
4	Civil	-	Fitting, Fixing & Supply of C.I Dresser Coupling in/c nut-bolts 200 mm dia Dresser Coupling in/c nut-bolts.	Each	16.000	1500.000	One Thousand Five Hundred	24000.000	Twenty-Four Thousand
5	Civil	-	Fitting , Fixing & Supply of C.I Flange Adopter 200 mm dia Flange Adopter including nut-bolts.	Each	6.000	2400.000	Two Thousand Four Hundred	14400.000	Fourteen Thousand Four Hundred
6	Civil	-	Fitting , Fixing & Supply of M.S Flange Adopter 200 mm dia MS Flange Adopter including nut-bolts.	Each	8.000	1500.000	One Thousand Five Hundred	12000.000	Twelve Thousand
7	Civil	-	Spindle (200 mm dia Sluice Valve-SS).	Each	10.000	3100.000	Three Thousand One Hundred	31000.000	Thirty-One Thousand
8	Civil	-	Body Gasket .	Each	48.000	400.000	Four Hundred	19200.000	Nineteen Thousand Two Hundred
9	Civil	-	Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract. Earthwork in excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead.	cum	15.000	170.000	One Hundred And Seventy	2550.000	Two Thousand Five Hundred And Fifty

10	Civil	-	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.5 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	cum	45.000	1000.000	One Thousand	45000.000	Forty-Five Thousand
11	Civil	-	Earth filling in foundation trenches and plinth in 150 mm layer with earth available within 90 m of the building site to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) including carrying watering, leveling, dressing and compacting to a specified percentage each layer up to finished level etc. all complete and accepted by Engineer-in-charge.	cum	45.000	200.000	Two Hundred	9000.000	Nine Thousand
12	Civil	-	Cleaning and disposing of excavated earth from the construction site by truck or by any other means to a place within 30 km radius of the city or town area including loading & unloading at both ends, leveling and dressing the carried earth etc. complete and accepted by the Engineer-in-charge.	cum	45.000	1025.000	One Thousand And Twenty-Five	46125.000	Forty-Six Thousand One Hundred And Twenty-Five
							Grand Total:	293275.000	Two Lakh Ninety-Three Thousand Two Hundred And Seventy-Five

This Bill of Quantities is Electronically Signed by Mr. Md. Islam on behalf of M/S. Al-Amin International