

M/S. Farha Trade International

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	--	N/A	Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also cover clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge.	Sqm	182.000	218.001	Two Hundred and Eighteen point Zero Zero One	39676.182	Thirty-Nine Thousand Six Hundred and Seventy-Six point One Eight Two	I have seen
2	--	N/A	Layout and marking for earthwork in excavation in foundation accepted by the Engineer-in-charge. [Plinth area of the structure shall be considered for measurement]	Sqm	159.250	19.001	Nineteen point Zero Zero One	3025.909	Three Thousand AND Twenty-Five point Nine Zero Nine	I have seen
3	--	N/A	"Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge."	Sqm	295.750	1088.001	One Thousand AND Eighty-Eight point Zero Zero One	321776.296	Three Lakh Twenty-One Thousand Seven Hundred and Seventy-Six point Two Nine Six	I have seen

4	--	N/A	Cutting jungles and shrub including removing and cleaning the spot/site	Sqm	455.000	9.001	Nine point Zero Zero One	4095.455	Four Thousand AND Ninety-Five point Four Five Five	I have seen
5	--	N/A	Carrying of rubbish, taking up all sorts of bricks, brick-bats and rubbish gravel chips, loading and unloading at both ends including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	Cum	455.000	178.001	One Hundred and Seventy-Eight point Zero Zero One	80990.455	Eighty Thousand Nine Hundred and Ninety point Four Five Five	I have seen
6	--	N/A	Supply of best and approved quality alluvial loamy silty soil including loading, unloading at both ends, properly stacking at site including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge.	Cum	16.200	913.001	Nine Hundred and Thirteen point Zero Zero One	14790.616	Fourteen Thousand Seven Hundred and Ninety point Six One Six	I have seen
7	--	N/A	Supply of well decomposed cow dung carried by trucks or any other means including loading, unloading at both ends, stacking the same at site including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge	Cum	8.100	1703.001	One Thousand Seven Hundred and Three point Zero Zero One	13794.308	Thirteen Thousand Seven Hundred and Ninety-Four point Three Zero Eight	I have seen
8	--	N/A	Labour charge for spreading the alluvial loamy silty soil from the stacks at site on the lawn surface, leveling, dressing the same including supply all necessary tools and plants etc. all complete and accepted by the Engineer-in-charge.	Cum	16.200	194.001	One Hundred and Ninety-Four point Zero Zero One	3142.816	Three Thousand One Hundred and Forty-Two point Eight One Six	I have seen
9	--	N/A	Levelling & dressing the compound or plant/flower bed as per direction of Engineer-in-charge.	Cum	455.000	9.001	Nine point Zero Zero One	4095.455	Four Thousand AND Ninety-Five point Four Five Five	I have seen
10	--	N/A	Dismantling of R.C.C. beam, lintel, column, drop wall, sun shade from any height and removal of debris to a safe distance	Cum	2.000	3928.001	Three Thousand Nine Hundred and Twenty-Eight point Zero Zero One	7856.002	Seven Thousand Eight Hundred and Fifty-Six point Zero Zero Two	I have seen
11	--	N/A	Safety measure item (gum boot = 4 pairs, visible vest = 4 nos, helmet = 4 nos, hand gloves = 4 pairs etc) . all complete and accepted by the Engineer-in-charge.	Item	1.000	3300.001	Three Thousand Three Hundred point Zero Zero One	3300.001	Three Thousand Three Hundred point Zero Zero One	I have seen
							Grand Total:	496543.495	Four Lakh Ninety-Six Thousand Five	

M/S. Farha Trade International**Tenderer's Quoted Price****Tenderer's Quoted Price**

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
496543.495	-5.000	471716.320	Four Lakh Seventy-One Thousand Seven Hundred and Sixteen point Three Two
	Grand Total:	471716.320	Four Lakh Seventy-One Thousand Seven Hundred and Sixteen point Three Two

This Tenderer's Quoted Price is Electronically Signed by Mrs. Kazi Jahan on behalf of M/S. Farha Trade International