

DS INTERNATIONAL

Priced Bill of Quantities (BOQ)

The following 50 (Fifty) Nos works Shall be Done by The Contractor who has Experience on Electrical Sub-Station Installation, Shifting, Repair and Maintenance works and Electric ABC License Holder. The bidder will complete the work within the least possible time. The Contractor will provide Free Service During Defect Liability Period of 12 (Twelve) Months of Concerning any Problem of this works. All Kind of Personal Protective Equipment (PPE) for the staffers will be provided by the bidder during this work.

Estimate by the Procuring Entity

Item no.	Group	Item Code (if any)	Description of Item	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	Select 'YES' to see the Grand Total
1	N/A	N/A	Disconnection & Reconnection/Feeder Shut Down of H.T line by concerned DESCO/DPDC including all expenditures related to this works .	P/Set	50.000	3500.001	Three Thousand Five Hundred Point Zero Zero One	175000.050	One Lakh Seventy-Five Thousand Point Zero Five	Yes
2	N/A	N/A	Withdrawal & laying of existing NYSEFGbY HT cable with in 3 feet depth & 2 feet wide cable other related works as per direction the Engineer-in-charge. (15m x 50 Sites) = 750 m.	P/m	460.000	455.001	Four Hundred And Fifty-Five Point Zero Zero One	209300.460	Two Lakh Nine Thousand Three Hundred Point Four Six	Yes
3	N/A	N/A	HT cable laying (lifting & downing) in presense of REB/DPDC's representative & install the cable in a secured place with supplying of necessary materials such as cable connector, GI wire, creampit etc. to complete as per direction of the Engineer-in-charge.	P/Item	22.000	4000.001	Four Thousand Point Zero Zero One	88000.022	Eighty-Eight Thousand Point Zero Two Two	Yes
4	N/A	N/A	Fitting and fixing of departmentally supplied 3x50 mm heat shrink termination kit at transformer and HT cable side.	P/Kit	38.000	5200.001	Five Thousand Two Hundred Point Zero Zero One	197600.038	One Lakh Ninety-Seven Thousand Six Hundred Point Zero Three Eight	Yes

5	N/A	N/A	Installing of DOFC supplied from division as per direction of the Engineer in charge.	P/Set	32.000	2000.001	Two Thousand Point Zero Zero One	64000.032	Sixty-Four Thousand Point Zero Three Two	Yes
6	N/A	N/A	Cleaning and servicing of X-former HT/LT bush as well as new cable connection to complete as per direction of the Engineer-in-charge.	P/Item	50.000	525.001	Five Hundred And Twenty-Five Point Zero Zero One	26250.050	Twenty-Six Thousand Two Hundred And Fifty Point Zero Five	Yes
7	N/A	N/A	Insulation megger testing of Transformer, LT-HT cable, sub pump motor, pump cable, VFD etc. as per direction of the Engineer-in-charge.	P/Item	50.000	2800.001	Two Thousand Eight Hundred Point Zero Zero One	140000.050	One Lakh Forty Thousand Point Zero Five	Yes
8	N/A	N/A	Repairing & maintenance of existing transformer fencing with welding, jointing & painting by contractor supplied paint-thinner etc.	Each	22.000	4400.001	Four Thousand Four Hundred Point Zero Zero One	96800.022	Ninety-Six Thousand Eight Hundred Point Zero Two Two	Yes
							Grand Total:	996950.724	Nine Lakh Ninety-Six Thousand Nine Hundred And Fifty Point Seven Two Four	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Emdad Sohag on behalf of DS INTERNATIONAL