

RAFIN CORPORATION

Price Schedule for Goods (Form e-PG2-3A)

A: PRICE OF GOODS (Including Spare Parts, if any) AND DELIVERY SCHEDULE

A: PRICE OF GOODS (Including Spare Parts, if any) AND DELIVERY SCHEDULE

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	"Inground Foot Lamp Item Description: Lamp (EPIGL-573) Watt: 6W, Life time: 50,000, Power Input: V AC-85-265, HZ: 50 PF: 0.95, CRI: 80, Light Colour: Warm "	nos	70.000	saidabad water treatment plant, Dhalpur, Dhaka.	90	BD/China	7788.000	Seven Thousand Seven Hundred And Eighty-Eight	545160.000	Five Lakh Forty-Five Thousand One Hundred And Sixty
2	Power Cable BYA 1CX1X1.5 mm2 RED CABLE	meter	410.000	saidabad water treatment plant, Dhalpur, Dhaka.	90	BD/China	130.000	One Hundred And Thirty	53300.000	Fifty-Three Thousand Three Hundred
3	Power Cable BYA 1CX1X1.5 mm2 BLACK CABLE	meter	410.000	saidabad water treatment plant, Dhalpur, Dhaka.	90	BD/China	130.000	One Hundred And Thirty	53300.000	Fifty-Three Thousand Three Hundred
4	10A Circuit Breaker HP	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	90	BD/China	1478.000	One Thousand Four Hundred And Seventy- Eight	5912.000	Five Thousand Nine Hundred And Twelve
5	6-way Distribution Board (DB)	nos	2.000	saidabad water treatment plant, Dhalpur, Dhaka.	90	BD/China	5984.000	Five Thousand Nine Hundred And Eighty-Four	11968.000	Eleven Thousand Nine Hundred And Sixty- Eight
6	PVC Pipe Electrical Wring Pipe 1.25"	meter	410.000	saidabad water treatment plant, Dhalpur, Dhaka.	90	BD/China	171.000	One Hundred And Seventy- One	70110.000	Seventy Thousand One Hundred And Ten
								Grand Total:	739750.000	Seven Lakh Thirty-Nine Thousand Seven Hundred And Fifty

This Price Schedule for Goods (Form e-PG2-3A) is Electronically Signed by Mr. A.K.M. Islam on behalf of RAFIN CORPORATION

RAFIN CORPORATION

Price Schedule for Related Services (Form e-PG2-3B)

B: PRICE OF RELATED SERVICES (Including Incidental services, if any) AND COMPLETION SCHEDULE

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Installation and Commissioning of Lighting System at Main Gate and other places of Saidabad WTP.	job	1.000	SWTP	90	BD	18040.000	18040.000	18040.000	Eighteen Thousand And Forty
2	Earthwork in excavation in foundation trenches up to 1.5 m depth and maximum 10 m head	cum	33.550	SWTP	90	BD	147.000	147.000	4931.850	Four Thousand Nine Hundred And Thirty-One Point Eight Five
3	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	cum	20.110	SWTP	90	BD	1026.000	1026.000	20632.860	Twenty Thousand Six Hundred And Thirty-Two Point Eight Six
4	One layer brick flat soling in foundation or in floor with first class/picked jhama bricks (BDS 208) including preparation of bed and filling the interstices with local sand, leveling etc. complete and accepted by the Engineer-in-charge	sqm	1.330	SWTP	90	BD	455.000	455.000	605.150	Six Hundred And Five Point One Five
5	Mass concrete in foundation (1:214) with brick chips and local sand of F.M. 1.2	cum	7.660	SWTP	90	BD	7820.000	7820.000	59901.200	Fifty-Nine Thousand Nine Hundred And One Point Two
6	Reinforced cement concrete works with minimum cement content relates to mix ratio 1:1.5:3 having maximum water cement ratio = 0.40 and minimum f _{cr} = 33.5 MPa, satisfying a specified compressive strength f _{cc} = 25 MPa at 28 days on standard cylinders as per standard practice of Code ACI/BNBC/ASTM, Cement conforming to BDS EN-197-1-CEM-I, 52.5N (52.5 MPa) / ASTM-C 150 Type I, best quality Sylhet sand or coarse sand of equivalent F.M. 2.2 and 20 mm down well graded stone chips conforming to ASTM C-33 (Aggregate grading as per table shown in technical specification), conducting necessary tests, making and placing shutter in position and maintaining true to plumb, making shutter water-tight properly, placing reinforcement in position; mixing with standard mixer machine with hopper, fed by standard measuring boxes, casting in forms, compacting by vibrator machine and curing at least for 28 days, removing centering-shuttering after specified time approved; including cost of water, electricity, other charges etc.all complete, approved and accepted by the Engineer-in-charge.	cum	1.100	SWTP	90	BD	13484.000	13484.000	14832.400	Fourteen Thousand Eight Hundred And Thirty-Two Point Four
7	Grade 400 (B400DWR / B420DWR: complying BDS ISO 6935-2:2016 / ASTM A615) ribbed or deformed bar produced and marked according to Bangladesh standard, with minimum yield strength, f _y (ReH)= 400 MPa but fy not exceeding 480 MPa and whatever is the actual yield strength within allowable limit as per BNBC/ ACI 318, the ratio of ultimate tensile strength f _u to yield strength f _y , shall be at least 1.25 and minimum elongation after fracture and minimum total elongation at maximum force is 17% and 8% respectively : up to ground floor.	kg	185.000	SWTP	90	BD	106.000	106.000	19610.000	Nineteen Thousand Six Hundred And Ten
								Grand Total:	138553.460	One Lakh Thirty-Eight Thousand Five Hundred And Fifty-Three Point Four Six