

Payment Invoice for 1st and Final Bill

Name of Work : Repair and maintenance of 315 mm, 225 mm and 160 mm dia water line leakage at Pagla, Kadomtoli, Donia, Shampur and Jatrabari area under MODS Zone-7, Dhaka WASA

Name of Contractor: M/s. M. V Six Brothers


Cont. No. 46.05.0000.412.90.019.23-89 Date: 22/06/2023

Item No.	Description of Items of Works	Unit	Qty	Unit rates or prices	Amount= (4x5)
1	2	3	4	5	6
1	Repairing of water line leakage for the excavation and removal of soft soil (on written permission of E/C) from the trench bottom beyond allowable depth and back fill of this by supplying, depositing and compaction in 150 mm layer of fine sand (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge.	cum	311.25	331.001	103,024.061
2	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutcha road surface.	cum	284.25	154.001	43,774.784
3	Repairing of water line leakage for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	cum	27.00	578.001	15,606.027
4	Extra over item 1 for completing temporary reinstatement of rigid and flexible paved road by compacted sand (FM 1.2) of 75 mm thick and one layer brick soling by full burned 1st class bricks of appropriate size (excavated bricks of proper sizes and quality is allowed to use) of the existing surfaced road in accordance with the technical specification and direction of Engineering in charge, and standard detail drawing for all water pipeline of any diameters for the type of road Surface given below.				
5	Asphalt/concrete road surface	sqm	10.00	74.001	740.010
6	Dismantle of R.C.C. Road and Removal of debris to a safe distance	cum	6.00	2790.001	16,740.006
	Shore protection work during excavation in foundation trenches to protect loss due to damage of property by Palisading beyond 1.5 m depth accepted by the Engineer [the rate is including cost of vertical post]	sqm	81.00	814.001	65,934.081



Item No.	Description of Items of Works	Unit	Qty	Unit rates or prices	Amount= (4x5) 6
1	2	3	4	5	6
7	300mm dia CI Dresser-Coupling in/c Nut-bolts	each	8.00	3019.001	24,152.008
8	200mm dia CI Dresser-Coupling in/c Nut-bolts	each	20.00	1668.001	33,360.020
9	150mm dia CI Dresser-Coupling in/c Nut-bolts	each	18.00	1411.001	25,398.018
10	225X225X225mm Tee	each	2.00	5345.001	10,690.002
11	225X160X225mm Tee	each	2.00	3900.001	7,800.002
12	160X110X160mm Tee	each	2.00	2460.001	4,920.002
13	90° PVC bend 225mm dia	each	2.00	4888.001	9,776.002
14	1 inch Bond Plug/End Cap	each	120.00	25.001	3,000.120
15	3/4 inch Bond Plug/End Cap	each	100.00	20.001	2,000.100
16	8 inch Clamp	each	32.00	500.001	16,000.032
17	6 inch Clamp	each	24.00	350.001	8,400.024
Total Amount=				391,315.300	

Total Amount (in word): Three Lakh Ninety One Thousand Three Hundred Fifteen Point Three Taka Only.


PAUL SARKER
 Sub-Assistant Engineer
 MODS Zone-7
 Dhaka WASA


 মোঃ আরফজামান হোসেন
 সহকারী প্রকৌশলী
 মডস জোন-৭
 ঢাকা ওয়াসা


 23/07/23
 মোঃ শাহ আলম
 নির্বাহী প্রকৌশলী
 মডস জোন-৭
 ঢাকা ওয়াসা।