

(227)

NURJAHAN ENTERPRISE

Section 6. Bill of Quantities

Bill of Quantities

Bill of Quantities

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price (In figures: BDT)	Unit Price (In words: BDT)	Total Price (In figures: BDT)	Total Price (In words: BDT)
1	-	N/A	Stripping of unserviceable plaster including racking, out joint, cleaning etc.	Sqm.	7.500	30.001	Thirty point Zero Zero One	225.008	Two Hundred and Twenty-Five point Zero Zero Eight
2	-	N/A	Providing minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	Sqm.	7.500	280.001	Two Hundred and Eighty point Zero Zero One	2100.007	Two Thousand One Hundred point Zero Zero Seven
3	-	N/A	"Exterior standard acrylic emulsion paint of approved best quality and color having water resisting properties and resistance properties against fungi, fading & flaking delivered from authorized local agent of the manufacturer (Berger weather coat smooth/Elite smooth exterior/ Asian apex weather coat or equivalent brand) in a sealed container; applying to exterior surface with surface preparation including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of exterior sealer of specified brand on prepared surface; then applying 1 coat of exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sandpaper/zero water paper;	Sqm	1282.710	268.001	Two Hundred and Sixty-Eight point Zero Zero One	343767.563	Three Lakh Forty-Three Thousand Seven Hundred and Sixty-Seven point Five Six Three

			finally applying 2 coats of exterior emulsion paint by spreading with brush/roller/spray machine & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge."						
4	-	N/A	Labour charge for tightening of old loose barbed wire fencing.	M	145.260	2.001	Two point Zero Zero One	290.665	Two Hundred and Ninety point Six Six Five
5	-	N/A	Standard synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in sealed container, having high water resistance, high bondability, flexibility properly; using specified brand thinner applying to metallic or wooden surface by brush/roller/spray in 2 coats over single coat antirust coating including cleaning, drying, making free from dirt, grease, wax, removing all chalk and scaled materials, all complete in all floors and accepted by the Engineer-in-charge. Standard synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in sealed container, having high water resistance, high bondability, flexibility properly; using specified brand thinner applying to metallic or wooden surface by brush/roller/spray in 2 coats over single coat antirust coating including cleaning, drying, making free from dirt, grease, wax, removing all chalk and scaled materials, all complete in all floors and accepted by the Engineer in charge.	Sqm.	613.548	225.001	Two Hundred and Twenty-Five point Zero Zero One	138048.914	One Lakh Thirty-Eight Thousand AND Forty-Eight point Nine One Four
6	-	N/A	Safety measure item (gum boot=3 Pairs, Visible vest=3Nos, Helmet=3Nos, Hand Gloves=3 Pairs & Net hessian Cloth=3 Pcs, Fly proof net=3Pcs, Safety Belt= 2 Nos. around Repaire, Maintenance & Painting work place (along the height of the wall) where public safety is likely to be endangered due to maintenance activities, which shall be supported using scaffolding around the	Item	1.000	1500.001	One Thousand Five Hundred point Zero Zero One	1500.001	One Thousand Five Hundred point Zero Zero One

painting/plaster including fitting
and fixing in position providing
necessary anchors, wires etc.
All complete and accepted by
the Engineer-in-charge.

**Grand
Total:**

485932.158

Four Lakh
Eighty-
Five
Thousand
Nine
Hundred
and Thirty-
Two point
One Five
Eight

*** Note: All applicable taxes, custom duties, VAT and other levies payable by the Contractor under the Contract shall be included in the unit prices submitted by the Tenderer.**

This Section 6. Bill of Quantities is Electronically Signed by Mr. Md. Shariful Islam on behalf of NURJAHAN ENTERPRISE