

BOQ

Operation & maintenance of different DMA under MODS Zone-6, Dhaka WASA, Lot-1 (Frame Work).

SI No	Description of Work	Unit	Qty	Unit Rate	Total Taka
1	2	3	4	5	6
1	De-wtering Pump : Hiring of dewatering Pump to remove water from District Meter Chamber (DMC) & required site as when and where necessary as per direction of the engineer-in-charge. (24 days x 2 nos)	day	48	1861.999	89,375.952
2	Labour Supply : Supply of Skilled labour for Repairing. Operation & Maintenance of water line, Sluice Valve Washout & DMC as per derrection of the Engineer-in charge. All Labour must were safety dress including WASA logo and contractors name etc.	person	450	646.999	291,149.550
3	Supply and fitting of 5/8" x 3" long M.S nut bolt including washer. complete as per direction of the E/c.	pcs	110	74.177	8,159.470
4	Supply and fitting of 1/2" x 2.5" long M.S nut bolt including washer. complete as per direction of the E/c.	pcs	100	33.749	3,374.900
5	Coloring/painting all device and equipments like sluice valve, NRV, PRV, PSV, BWM etc. inside the chamber by removing all rust and dust with properly brushing etc as per direction of E/C.	Each	25	2499.999	62,499.975
6	Protection for safety : The site must be protected from all side by bamboo, Safety net & red tape. Traffic must be managed and controlled keeping vehicle movement normal during the work as per direction of engineer-in-charge.	Nos	40	999.999	39,999.960
Total Tk. =					494,559.807

Abstract of Cost

1	Operation & maintenance work	Tk. =	494,559.807
2	(-) Less 5.00% As per schedule	Tk. =	24,727.990
		Tk. =	469,831.817

Inwords: Four lakh sixty-nine thousand eight hundred and thirty-one point eight one seven taka only.