

Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.

Name of Works : Repairing Of HDPE Water Line Leakage & Removal dirty Water In Front Of House no- 64, Road no- 16, DIT Project, Merul Badda (DMA-805) under MODS Zone-8, Dhaka WASA.

Sl. No.	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	160 mm dia HDPE Pipe	7.00	P/M			Supply by Sub store
2	160 mm dia HDPE Sleeve E.F	2	Nos	5000.00	10,000.00	
3	Earth work: (3.50*7.50*1.52)= 39.90 cum	39.90	Cum	149.00	5945.10	
4	Supply, depositing and compaction of fine sand (FM 0.8) bedding surrounding and above pipe (3.50*7.50*1.52)= 39.90 cum	39.90	Cum	503.00	20069.70	
5	Mechanics Charge	2	P/Person	1000.00	2000.00	
6	Daily Labour	10	P/Person	800.00	8000.00	
7	Hire charge of de-watering pump	2	P/Day	1862.00	3724.00	
Total					49738.80	
Say Total (Tk.)					49739.00	

In words: Forty Nine Thousand Seven Hundred Thirty Nine Taka Only.

১০/০৬/২৬
 আব্দুল হোসেন
 উপ-সহকারী প্রকৌশলী
 মডস জোন-৮
 ঢাকা ওয়াশা।

১০/০৬/২০২৬
 খ.র জালালুদ্দীন রহমান
 উপ-বিভাগীয় প্রকৌশলী
 মডস জোন-৮
 ঢাকা ওয়াশা।

১০/০৬/২০২৬
 মোঃ আব্দুল মজিদ
 নির্বাহী প্রকৌশলী
 মডস জোন-৮
 ঢাকা ওয়াশা।