

M/S. SAMI INTERNATIONAL**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	N/A	Stopping of roof leakage of C.I. sheet roof with putty	kg	1498.000	200.001	Two Hundred point Zero Zero One	299601.498	Two Lakh Ninety-Nine Thousand Six Hundred and One point Four Nine Eight	I have seen
2	Civil	N/A	Labour for taking out C.I Sheet roofing	sqm	406.000	40.001	Forty point Zero Zero One	16240.406	Sixteen Thousand Two Hundred and Forty point Four Zero Six	I have seen
3	Civil	N/A	0.27mm thick galvanized iron plain Sheet ridging with 300 mm lap on either side fitted and fixed with galvanized bolts and nuts etc. same in proper position as per direction of the Engineer-in-charge.	m	37.000	443.001	Four Hundred and Forty-Three point Zero Zero One	16391.037	Sixteen Thousand Three Hundred and Ninety-One point Zero Three Seven	I have seen
4	Civil	N/A	Labour for taking out and refitting of old G.I. Ridge/valleynd	sqm	245.000	189.001	One Hundred and Eighty-Nine point Zero Zero One	46305.245	Forty-Six Thousand Three Hundred and Five point Two Four Five	I have seen
5	Civil	N/A	Re-fabrication of existing mild Steel section as per design constructed. hoisting fitting and fixing in position with bolts and nuts or rivets or welded etc. complete and accepted by the Engineer.	kg	585.000	180.001	One Hundred and Eighty point Zero Zero One	105300.585	One Lakh Five Thousand Three Hundred point Five Eight Five	I have seen
6	Civil	N/A	Removal/Shifting of existing materials to safe distance from working site and re-stacking old heavy weight goods like gate bulbs, Switch bulbs, old transformers the same after completion of works as per	lot	1.000	80000.001	Eighty Thousand point Zero Zero One	80000.001	Eighty Thousand point Zero Zero One	I have seen

			direction of the Engineer-in-charge.							
7	Civil	N/A	Manufacturing, supplying, fitting and fixing M.S. grill fencing as per design with outer frames having 38 mm x 38 mm x 6 mm M.S. angle and inner members having 6 mm dia M.S. rod placed @ 110 mm c/c diagonally on both direction, welding each criss-cross end of rod with corners of outer frame including cutting rods and size angles to required shapes and size and setting the entire fence with the previously installed box tube (box tube made with 2 nos. angle) post including thorough and full welding the frame with the angle box posts, painting 2 coats of synthetic enamel paint over a coat of anti-corrosive priming etc. all complete as per drawing and accepted by the Engineer-in-charge. (Rate is excluding the cost of angle box tube post and its installation and excluding the cost of paint)	sqm	79.200	2536.001	Two Thousand Five Hundred and Thirty-Six point Zero Zero One	200851.279	Two Lakh Eight Hundred and Fifty-One point Two Seven Nine	I have seen
8	Civil	N/A	Site Cleaning	item	1.000	29509.949	Twenty-Nine Thousand Five Hundred and Nine point Nine Four Nine	29509.949	Twenty-Nine Thousand Five Hundred and Nine point Nine Four Nine	I have seen
							Grand Total:	794200.000	Seven Lakh Ninety-Four Thousand Two Hundred	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mrs. BANIN ISLAM on behalf of M/S. SAMI INTERNATIONAL

M/S. SAMI INTERNATIONAL**Tenderer's Quoted Price**

Tenderer's Quoted Price			
Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
794200.000	-5.000	754490.000	Seven Lakh Fifty-Four Thousand Four Hundred and Ninety
	Grand Total:	754490.000	Seven Lakh Fifty-Four Thousand Four Hundred and Ninety

This Tenderer's Quoted Price is Electronically Signed by Mrs. BANIN ISLAM on behalf of M/S. SAMI INTERNATIONAL