

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer
Civil Maintenance Division
Dhaka WASA, Dhaka
6th floor, WASA Bhaban
98 Kazi Nazrul Islam avnue, Dhaka.

Name of the Work: Making a security post by C.I sheet, angle and ancillary works at Gulshan officers quarter.

Item No.	PWD 2022	Description of Items of Works	Unit	Quantity	Unit rates or prices	Amount
1	10.20	Supply and installation of 0.47 mm thick zinc alum color coated profile sheet of durability class 2 with minimum warranty period of 10 years of durability, for roof, wall, capping, flashing, trimming, gutter etc. conforming to ASTM A792, Grade: 80, AZ150 gm/m ² , including the cost of necessary accessories (sheeting screws with washers, silicon sealant etc.), testing of materials etc. all complete as per drawing specification and direction of Engineer-in-charge (supplier has to produce papers to proof the source of material).	sqm	64.000	322	20,608
2	08.7.1	Manufacturing, supplying, fitting and fixing Expansion Joint for gap upto 100mm with 125mmx50mmx6mm and 75mmx50mmx6mm galvanized MS angle and 8mm thick galvanized MS plate etc. all complete as per drawing, design and accepted by the Engineer-in-charge.	meter	2.000	7765	15,530
3	21.3.2	16" sweep (Plastic body and blade)	each	1.000	2687	2,687
4	1.8.1.3	1C-2x4 sqmm (BYM) cable with 4 sqmm (BYA) ECC wire	meter	14.000	301	4,214
5	18.1.1	Supplying, fitting and fixing plain Particle board ceiling (Drop/Plain) (complying unit wt 499 to 550 kg/m ³ , bending strength 0.35 N/mm ² , max swelling 8%, moisture content not more than 10%), of 12 mm thick with best quality and well seasoned Garjan wood frame of section 50 mm x 38 mm at 600 mm x 600 mm in grid suspended from ceiling or roof or beam by 12 SWG double ply G.I. wire fixed to the ceiling by rowel plug, screws, hooks, nails etc, maintaining straight lines and desired finished level at bottom face including vertical strut as required, cutting holes in slabs or beams by electric drill machine and mending good the damages, if any during execution of the work, including the provisions of lighting arrangement, also including cost and carriage of all materials, accessories, labour for installation, electricity charge, scaffolding, screws, nails, with best quality and approved colour etc. All complete, as per drawing design and accepted by the Engineer-in-charge. All sizes of wood are finished. All Garjan wood frames must be protected from termites, cockroach and other insects. Measurement will be taken as per finished surface area. The brick/ RCC surface shall be dry and damp-proof. (Rate is excluding cost of polish/ paint etc. of any type).	sqm	2.000	2832	5,664
Total:						48,703

In word: forty eight thousand seven hundred three taka only

সমিতি
6/6/23
রাজিয়া সুলতানা
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।

Rohatun
09.08.23
রাহাত উন নবী
সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।

সাহা
09.08.23
মুজা সাহা
নির্বাহী প্রকৌশলী
সিএম বিভাগ
ঢাকা ওয়াশা।