

DHAKA WATER SUPPLY & SEWAGE AUTHORITY**Office of the Executive Engineer****MODS Zone-7, Dhaka WASA****107/1/A/1/A, North Jatrabari****Near Ideal School and College, Dhaka.****Phone : 7547929****Payment Invoice**

Name of work: Rising, Repairing and Maintenance of boundary wall at Smrity dhara, Muradpur and others water pump under MODS Zone-7 area, Dhaka WASA.

Name of Contractor: M/S. mohammad Mowla.

Reference to Agreement: **Contract No- 46.05.0000.412.92.011.23-C-04, Date: 26/07/2023.**

Work order reference : 46.05.0000.412.92.011.23-59, Date : 26/07/2023.

Date of actual completion of work: **05.08.23**

Reference to recorded MB Book No: **41/22/Zone-7**

MB Book Page: **15** to **16**

Item No.	Description of Articles	Unit	Quantity	Rate	Amount
1	Brick works with first class bricks in cement sand (F.M. of sand 1.2) mortar (1:6) in foundation and plinth, filling the joints/interstices fully with mortar, racking out the joints, cleaning and soaking the bricks at least for 24 hours before use and curing at least for 7 days etc. all complete including cost of water, electricity and other charges and accepted by the Engineer. (Cement: CEM-II/A-M)	cum	1.000	6040.000	6040.000
2	125 mm brick works with first class bricks with cement sand (F.M. 1.2) mortar (1:4) and making bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge.	sqm	9.072	948.000	8600.256
3	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge.	sqm	31.854	243.000	7740.522
4	Colour wash with yellow orchard/any other colour pigment by two coats over a prime coat of white wash, lime mixture prepared at least 12 hours before use, slacking stone lime, supply of gums, blue, stirring thoroughly, removing the floating materials from the mixer, surface cleaning to free from all foreign materials before application of each coat, applying one vertical and one horizontal wash for each coat and successive coat is to be applied after drying up of previous coat including hair brass, providing necessary scaffolding and cleaning plinth, floors, doors, windows, portions and ventilators by washing, rubbing, oiling if necessary after white wash for all floors including cost of water, electricity and other charges etc. complete in all respect in all floors and accepted by the Engineer.	sqm	31.854	25.000	796.350

5	Standard synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer (Berger jhlik synthetic enamel/Elite quick drying/Asian decora synthetic enamel or equivalent brand) in a sealed container, having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in 2 coats over single coat anti-corrosive coating including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.	sqm	11.928	189.000	2254.392
6	Supplying, fitting, fixing, and installation of ordinary type M.S. gate (double leaf) of any design and shape with 38 x 38 x 6 mm M.S. Angle outer frame having 16 mm dia M.S. rod placed vertically @ 75 mm c/c. at bottom part and top part (arrows) and also placed horizontally at bottom for interconnection of 16 mm dia M.S. rod placed vertically as per design, the top part covered with 18 BWG M.S. sheet and fixed with 4 Nos. 38 x 6 mm F.I. bars placed diagonally and 4 Nos. 38 x 6 mm F.I. bars placed horizontally and vertically all passing through the center, providing locking arrangements on 3 mm thick M.S. plate one for main gate and one for minimum 300 x 1025 mm pocket gate with 38 x 38 x 6 mm M.S. angle and 16 mm dia M.S. rod placed vertically @ 75 mm c/c, providing 38 x 38 x 6 mm M.S. angle clamps fitted and fixed with the outer frame of the main gate, the clamp being embedded in R.C.C. or R.C.C. core pillar with cement concrete (1:2:4) in masonry including cutting holes and mending good the damages, finishing, curing etc. including riveting, welding as and where necessary, painting two coats with approved quality of synthetic enamel paint over a coat of priming of anti-corrosive paint etc. all complete as per drawing, design and accepted by the Engineer.	sqm	11.620	6036.000	70138.320
So, Total bill amount to be paid:					95569.840

In Words: Ninety five thousand five hundred sixty nine point eight four zero taka only.

Hgdk
06.08.23

Sub-Assistant Engineer
MODS Zone-7
Dhaka WASA.

mgdk

Assistant Engineer
MODS Zone-7
Dhaka WASA.

06/08/23

Executive Engineer
MODS Zone-7
Dhaka WASA.