


Office of the Executive Engineer
MODS Zone-9, Dhaka WASA
Plot# 19, Shahajalal Avenue, Sector# 6, Uttara Dhaka
Estimate

Name: Repairing of leakage at Delivery line of Uttara-1 Water pump under MODS Zone-9, Dhaka WASA.

SL No	Description of the item	Unit	Quantity	Rate(Tk.)	Amount (Tk.)
1	MS Pipe (Seamless) 200mm dia	P/M	4	3888	15552.000
2	Extra-over item 1 for supply and lay of Ductile/cost iron dresser type flexible coupling/adapters for the pipe materials and diameter given below in accordance with the technical specification and the standard detail drawing. 200 mm dia Dresser Coupling in/c nut-bolts	P/Nr	4	1600	6400.000
3	Bedding and surrounding by river saturated Sand. $(10*0.6*0.76) - ((3.14*20^2)/4)*10 + ((1.52*1.52*.60)*3) = 8.40m^3$	cum	8.4	503	4225.200
4	Backfilling $10*0.76*0.91 + (3*(1.52*1.52*0.91)) = 13.23m^3$	cum	13.23	134	1772.820
5	Excavation $(10*0.76*1.52) + (3*(1.52*1.52*1.52)) = 22.08m^3$	cum	22.08	288	6359.040
6	M.S bend 45° 200mm dia	Each	1	6545	6545.000
7	Hire charge of de-watering Pump	P/day	2	1862	3724.000
8	Safety Barriers	LS	LS	4000	4000.000
				Total	48578.060

In Word: Forty Eight Thousand Five Hundred Seventy Eight point Zero Six Zero Taka only.


07-8-23
জহিরুল ইসলাম
উপ-সহকারী প্রকৌশলী
মডুস জোন-৯
ঢাকা ওয়াসা


07/08/2023
মোঃ ফারুক হোসেন
সহকারী প্রকৌশলী
মডুস জোন-৯
ঢাকা ওয়াসা


07-08-23
(মোঃ মোজাহিদুর রহমান)
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডুস জোন-৯, ঢাকা ওয়াসা