

**Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.**

Name of Works : Repairing Of Water Line Leakage & Removal dirty Water in front of Khilbarirtek auto stand at MODS Zone-8, Dhaka WASA							
Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	160 mm dia HDPE Pipe	6.00	P/M			Supply by Sub store
4	Approved Rate	160 mm dia HDPE Sleeve E.F	2.00	Nos			Supply by Sub store
7	Approved Rate	Excavation and removal of soil from the trench bottom beyond allowable depth in accordance with the technical specification and direction of Engineering in charge,	33.256	Cum	331.000	11007.736	
8	Approved Rate	supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	33.156	Cum	578.000	19164.168	
9	Approved Rate	One layer brick flat soling in foundation with first class/picked jhama bricks (BDS 208) including preparation of bed and filling the interstices with local sand, leveling etc.	15.520	p/sqm	636.001	9870.736	
10	Approved Rate	Skilled Technician	3.00	P/Person	1000.00	3,000.00	
11	Approved Rate	Labour Charge	6.000	P/Person	800.000	4800.000	
Total=						47842.640	


In words: Forty Seven Thousand Eight Hundred Forty Two point Six Four Zero TK Only


17.08.26

ইমরুল ইসলাম
উপ-সহকারী প্রকৌশলী
মডুস জোন-০৮, ঢাকা ওয়াসা।


17.08.26

মোঃ গোলাম মোস্তফা হককার
উপ-বিভাগীয় প্রকৌশলী
মডুস জোন-৮, ঢাকা ওয়াসা।


17/08/26

অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডুস জোন-৮
ঢাকা ওয়াসা।