

Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.

Name of Works : Repairing Of HDPE Water Pipe Leakage & Removal dirty Water H#25, R#01, Block#E, Sector#1 Aftabnagar (DMA-806) under MODS Zone-8, Dhaka WASA.

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	160 mm dia HDPE Pipe	2.50	P/M			Supply by Sub store
2	Approved Rate	160 mm dia HDPE Sleeve E.F	5	Nos	5000.000	25,000.000	
3	Approved Rate	Earth work in Excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead (2*4*2.2*1.65)= 29.04 cum	29.040	Cum	168.00	4,878.720	
4	Approved Rate	Repairing of water line leakage for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters. (2*4*2.2*1.65)= 29.04 cum)/2=14.52 cum	14.520	Cum	578.000	8,392.560	A11:J23
5	Approved Rate	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutchra road surface (2*4*2.1*1.65)= 29.04 cum)/2=14.52 cum	14.520	Cum	154.000	2,236.080	
6	Approved Rate	B)Removal of excavated earth/debris etc (2*4*2.1*1.65)= 29.04 cum)/2=14.52 cum	14.520	Cum	288.000	4,181.760	
7	Approved Rate	Mechanics Charge	2	P/Person	1000.000	2,000.000	
8	Approved Rate	Hire charge of de-watering pump	1	P/Day	2141.301	2,141.301	
Total Tk=						48830.421	

In words: Forty Eight Thousand Eight Hundred & Thirty Point Four Two One Taka Only.

[Signature]
20.08.26

[Signature]
20.08.26

মোঃ মোস্তফা
সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াশা

[Signature]
20.08.26

অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াশা।