

M/S. Raihan Construction**Price Schedule for Goods (Form e-PG2-3A)****A: PRICE OF GOODS (Including Spare Parts, if any) AND DELIVERY SCHEDULE****A: PRICE OF GOODS (Including Spare Parts, if any) AND DELIVERY SCHEDULE**

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Supply of stainless steel(S.S) flat bar screen with related accessories(like Top base plate, Bottom base plate, Middle channel, Side angle bar, Flat bar, Shaft, Bush, Nut-bolt for bush, Clamp bar, Triangular bar, Nut-bolt for shaft, Washer etc) at Narinda CPS inlet chamber(North side middle part). Type: Flat S.S bar screen, Operation: Manual raking, Screen size: W2100mm x H2820mm(63.74 sqft), Installation angle: 60 degree, Spacing between bars: 50mm, Details As per attached Drawing & Technical Specifications and Compliance of Goods and related services (Form e-PG2-4)	sqft	63.740	Divisional store of PSTP	45	India	37750.000	Thirty-Seven Thousand Seven Hundred And Fifty	2406185.000	Twenty-Four Lakh Six Thousand One Hundred And Eighty-Five
								Grand Total:	2406185.000	Twenty-Four Lakh Six Thousand One Hundred And Eighty-Five

This Price Schedule for Goods (Form e-PG2-3A) is Electronically Signed by Mr. Md. Raihan on behalf of M/S. Raihan Construction

M/S. Raihan Construction**Price Schedule for Related Services (Form e-PG2-3B)****B: PRICE OF RELATED SERVICES (Including Incidental services, if any) AND COMPLETION SCHEDULE**

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	"Hire Charge for engaging 7 (seven) members divers team for collecting and lifting sludge, solid compacted elements and semi solid elements from the invert of storm sewer/Box culvert/sludge gate etc. for removing the water blockage by diving. The diving team must be well equipped with proper safety such as Oxygen cylinder, gas mask, pumping arrangement etc all complete. The contractor will be liable for any accident for this purpose. So that they should be taken sufficient precaution to avoid any kind of accident. All complete as per direction of the Engineer-in-charge."	Day	10.000	Narinda CPS	45	Bangladesh	500.000	500.000	5000.000	Five Thousand
2	Fitting & fixing of De-watering pump Bailing out of all shorts of water from Trances, cannel the line with all lead & lift by the required nos of 5 Cusec capacity de-watering pump should be use usually, including supplying the fuel, lubricants spares & all other required accessories & man power etc. all complete as per direction of the Engineer ?in-Charge	Hours	160.000	Narinda CPS	45	Bangladesh	50.000	50.000	8000.000	Eight Thousand

3	Making cross bundh of required height & width for the purpose of dewatering and keeping the site always workable, with sand/ soil & empty bags arranged by the contractor and maintaining the same till the completion of work including supply of necessary planks, runner hings etc. with necessary equipments & removal the same accorately after completion of work asper direction of the Engineer-in-charge.	Each	2.000	Narinda CPS	45	Bangladesh	500.000	500.000	1000.000	One Thousand
4	Cleaning the following sizes pipe drain/Brick sewer manhole catch pits etc. including removing the bund inside the line manhole cleaning the solid semi-solid & slushy earth, debris, polythene and any other foreign materials by manually labour by using ladder or by any other means, from the existing base of the line, without making any damage to the structure, including supply of all necessary equipments materials if necessary to ensure the proper cleaning along the whole length & width up to the invert level of the line and removing the sludge & debris to safe distant place without causing any disterbence to the traffic etc. all complete as per direction the E/C. e) 1050 mm dia and Above	cum	820.000	Narinda CPS	45	Bangladesh	50.000	50.000	41000.000	Forty-One Thousand
5	Removal of Pipe line and Brick sewer sludge from the cleaning site up to the nearest D.C.C. dumping	cum	738.000	Narinda CPS	45	Bangladesh	50.000	50.000	36900.000	Thirty-Six Thousand Nine Hundred

	yard carrying loading unloading etc. complete as per direction of the Engineer-in-charge.									
6	Related services(withdrawn the damaged screen and Installation, Testing & commissioning of new supplied screen by engaged skilled & experienced Engineers, electro-mechanical technical team and necessary equipments, materials & tools etc.)	Job	1.000	Narinda CPS	45	Bangladesh	500.000	500.000	500.000	Five Hundred
								Grand Total:	92400.000	Ninety-Two Thousand Four Hundred

This Price Schedule for Related Services (Form e-PG2-3B) is Electronically Signed by Mr. Md. Raihan on behalf of M/S. Raihan Construction

<u>M/S. Raihan Construction</u>	
Discount Form	
Unconditional Discount Form	
Discount in Percentage (%) [in Figure]	Discount in Percentage (%) [in Word]
16.570	Sixteen Point Five Seven
16.570	Sixteen Point Five Seven

This Discount Form is Electronically Signed by Mr. Md. Raihan on behalf of M/S. Raihan Construction