



M/S. HOWLADER FOUNDATION

General Marchant *Contractor *Builders *Supplier *Importer & Exporter.

নির্বাহী প্রকৌশলী

মডুস জোন- ৯

ঢাকা ওয়াসা।

তারিখ- ০৬/০৮/২৩ ইং।

বিষয় : Leakage detection and repair-maintenance of 110 mm dia water line at Uttara land office Dalipara, Uttara Dhaka, under MODS Zone-9, Dhaka WASA. কাজের ১ম চলতি ও চূড়ান্ত বিল প্রদান প্রসঙ্গে।

সূত্র: ১। কার্যাদেশ নং-৪৬.০৫.০০০০.৪১৪.২৬.০৫৯.২৩-২০ তারিখ: ০২/০৮/২৩ ইং।

উপরোক্ত বিষয় ও সূত্রের প্রেক্ষিতে জানানো যাচ্ছে যে, Leakage detection and repair-maintenance of 110 mm dia water line at Uttara land office Dalipara, Uttara Dhaka, under MODS Zone-9, Dhaka WASA. কাজটি নির্ধারিত সময়ের মধ্যে (০৫/০৮/২৩ ইং) সিডিউল মোতাবেক শুষ্ঠভাবে সম্পন্ন করেছি। মোট বিলের পরিমান ট-৪৯,৪১৭.২৬/- (উনপঞ্চাশ হাজার চারশত সতের দশমিক দুই ছয়) টাকা মাত্র।

Sl No	Rate Schedule	Description of the item	Quantity	Unit	Rate	Amount
		37 mm dia HDPE Pipe	25	Meter	185.001	4625.025
		50 mm dia HDPE Pipe	5	Meter	450.001	2250.005
		110 mm dia HDPE Pipe	1	Meter	2,024.001	2024.001
		110 mm dia HDPE Sleeve	2	Each	1,923.001	3846.002
2	2.10.1(PWD)	Sand filling n foundation trenches and plinth with sand having minimum F.M.0.5 in 150 mm tayers rnduding leveling, ateing and compaction lo achieve minmum dry density of 95% with optimum molslure	9.60	Cum	1,088.001	10444.810
3	2.9 (PWD)	Extra -over item I for the excavation and removal of loose soil from site and the back fill of the excess excavation with approved with the technical specification.	9.60	Cum	1,054.001	10118.410
4	Pre-Approved Rate	Hire Charge of 1.5 KVA mobile Generator.for power supply to drive electrofusion machine. Including fuel and operators all complete as per direction of the E/C.	1	Per/day	2,000.001	2000.001
5	Pre-Approved Rate	Hire Charge of electrofusion machine to joint sleeve in the excavation. all complete as per direction of the E/C.	1	Per/day	1,500.001	1500.001
6	WASA R.S-18	Hire Charge of de-watering pump. Bailing out of all from pipe line trench with supply of De- watering pump required size including supplying of fuel, lubricants and all other required accessories & manpower to keep the trench in a dry condition at all times etc. all complete as per direction of the E/C.	2	Per/day	1,862.001	3724.002
7	WASA R.S-16	Connection of existing house service line to new water main at all depth in accordance with the technical specification for the diameter of service line giver below.				
		c) DN- 20 to DN 25 mm dia	4	Each	1,216.001	4864.004
		d) DN- 32 to DN 50 mm dia	1	Each	2,021.001	2021.001
8	LS	Road Safety measures and tools as per direction of Engineer in Charge	1	Each	2000.001	2000.00
Total Tk=						49,417.26

In Word- Forty Nine Thousand Four Hundred Seventeen Point Two Six Taka Only

এমতাবস্থায় আমার দাখিলকৃত আলোচ্য কাজের কার্যসমাপ্তির রিপোর্ট গ্রহন ও ১ম চলতি ও চূড়ান্ত বিল নানদ সর্বমোট ট-৪৯,৪১৭.২৬/- (উনপঞ্চাশ হাজার চারশত সতের দশমিক দুই ছয়) টাকা পরিশোধের ব্যাবস্থা গ্রহন করতে একান্ত মঞ্জি হয়।

বিলটি স্বীকৃতি করা হয়েছে। পরিমান ঠিক আছে। তারপরও করা যাবে না।

মোঃ নাজমুল হুসাইন
উপ-সহকারী প্রকৌশলী
মডুস জোন-৯
ঢাকা ওয়াসা

মোঃ ফারুক হোসেন
সহকারী প্রকৌশলী
মডুস জোন-৯

মোঃ মোজাহিদুর রহমান
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডুস জোন-৯, ঢাকা ওয়াসা

M/S. Howlader Foundation