


**Office of the Executive Engineer**  
MODS Zone-9, Dhaka WASA

**Estimate**

Name of the Work: Cleaning of 6 Nos pump compound under MODS Zone-9, Dhaka WASA.

| SL No     | Item code | Description                                                                                                                                                                                                                                                                                                                                                                                             | Unit   | Qty.    |        | Amount (TK) |
|-----------|-----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|--------|-------------|
| 1         | 2.10.1    | Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge (3*.5*6=9 m3. | Cum    | 10 m3   | 1088   | 10,880.00   |
| 2         | MR        | Labor for cleaning and removing rubbish and weeds from pump compound and pump house.                                                                                                                                                                                                                                                                                                                    | Nos    | 28 Nos  | 850.00 | 23,800.00   |
| 3         | MR        | Vehicle Rent (for remove of rubbish from pump house to farther distant/disposal point. )                                                                                                                                                                                                                                                                                                                | P/Trip | 12 Trip | 1250   | 15,000.00   |
| Total Tk= |           |                                                                                                                                                                                                                                                                                                                                                                                                         |        |         |        | 49,680.00   |

In Word- Forty Nine Thousand Six Hundred Eighty Taka Only.

  
26.07.23  
**Md. Nazmul Hussain**  
Sub-Assistant Engineer  
MODS Zone-9  
Dhaka WASA

  
26.07.23

মোঃ ফারুক হোসেন  
সহকারী প্রকৌশলী  
মডস জোন-৯  
ঢাকা ওয়াসা

  
30.07.23  
(মোঃ মোজাহিদুর রহমান)  
নির্বাহী প্রকৌশলী (চঃ দাঃ)  
মডস জোন-৯, ঢাকা ওয়াসা