

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer

Civil Maintenance Division

Dhaka WASA, Dhaka

6th floor, WASA Bhaban

98 Kazi Nazrul Islam avnue, Dhaka.

Name of the Work: Raising boundary wall and ancillary repair works of MD house at Gulshan-2.

Item No.	Group	PWD 2022	Description of Items of Works	Unit	Quantity	Unit rates or prices	Amount
1	Civil	04.16	125 mm brick works with first class bricks with cement sand (F.M. 1.2) mortar (1:4) and making bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) In ground floor	16.950	sqm	1185.001	20085.767
2	Civil	15.1.2	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to outer surface of wall , finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.	37.190	sqm	316.001	11752.077
3	Civil	16.1.1	Exterior standard acrylic emulsion paint of approved best quality and color having water resisting properties and resistance properties against fungi, fading & flaking delivered from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary exterior sealer of specified brand on prepared surface; then applying necessary exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	37.19	sqm	274.001	10190.097


স্বাক্ষর
২/৬/২৬
সাজিয়া সুলতানা
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।

স্বাক্ষর
০৯.০৮.২৩
রাহাত উন নবী
সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।


স্বাক্ষর
০৯.০৮.২৩
মুজ্জা সাহা
নির্বাহী প্রকৌশলী
সিএম বিভাগ
ঢাকা ওয়াশা

4	Civil	21.8	Supplying, fitting and fixing 12 BWG barbed wire (2 ply, 4 points) in fencing work @ 150 mm c/c both horizontally and vertically, supported by 38 mm x 38 mm x 6 mm M.S. Y-shape angle post (300 mm embedded in R.C.C. or in brick work with a cement concrete base of 75 mm x 75 mm x 300 mm) 600 mm vertical and 450 mm inclined or as per requirement @ 2.4 m c/c including straightening, binding the joints with 18 BWG wire, making holes in the angle etc. including supplying all necessary materials complete in all respect and accepted by the Engineer-in-charge. (Rate is excluding the cost of paint, R.C.C./brick work or C.C. which is to be paid as per corresponding items in the schedule).	6.620	sqm	1034.001	6845.087
							Total: 48,873.028
							say 48,873.000

In word: (Forty eight thousand eight hundred seventy three) taka only


 ২/৮/২৬
 রাজিয়া সুলতানা
 উপ-সহকারী প্রকৌশলী
 সি এম বিভাগ
 ঢাকা ওয়াশা।


 09.08.23
 রাহাত উন নবী
 সহকারী প্রকৌশলী
 সি এম বিভাগ
 ঢাকা ওয়াশা।


 09.08.23
 মুজা সাহা
 নির্বাহী প্রকৌশলী
 সিএম বিভাগ
 ঢাকা ওয়াশা।