

Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.

Name of Works : Repairing Of 160 mm Dia HDPE Water Pipe Leakage at Plot#46, Block# F Aftabnagar (DMA-806) under MODS Zone-8, Dhaka WASA.

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	160 mm dia HDPE Pipe	2.50	P/M			Supply by Sub store
2	Approved Rate	160 mm dia HDPE Sleeve E.F	4	Nos	5000.000	20,000.000	
3	Approved Rate	Earth work in Excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead (2*3*2.90*2.00)= 34.80 cum	34.800	Cum	168.00	5,846.400	
4	Approved Rate	Repairing of water line leakage for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters. (2*3*2.90*2.00)= 34.80 cum)/2=17.4 cum	17.400	Cum	578.000	10,057.200	
5	Approved Rate	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutchra road surface (2*3*2.90*2.00)= 34.80 cum)/2=17.4 cum	17.400	Cum	154.000	2,679.600	
6	Approved Rate	B)Removal of excavated earth/debris etc(9.15*2.90*1.55)= 41.130 cum)/2=20.565 cum	17.400	Cum	288.000	5,011.200	
7	Approved Rate	Mechanics Charge	2	P/Person	1000.000	2,000.000	
8	Approved Rate	Hire charge of de-watering pump	2	P/Day	2141.301	4,282.602	
Total Tk=						49877.002	

In words: Forty Nine Thousand Eight Hundred Seventy Seven Point Zero Zero Two Taka Only.


28.07.26
মোঃ আরিফুর রহমান
উপ-সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।


28.07.26
মোঃ মোস্তফা
সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।


28.07.26
জনাব নূরুল কামরুজ্জামান
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।