


Office of the Executive Engineer
MODS Zone-9, Dhaka WASA

Plot # 19, Shajalal Ave., Sector # 6, Uttara.


Cost of Estimate : Repairing of leakage at KC Model School Rd & Mia Box Rd,
Dokkhinkhan area under MODS Zone-9, Dhaka WASA.

Sl. No.	Description Of Item	Quantity	Unit	Rate (TK)	Amount (TK)
1	75 mm dia HDPE Pipe	3	P/M	1900.00	5700.00
2	75 mm dia HDPE Sleeve E.F	4	Each	2,100.00	8,400.00
3	Generator & Electro-Fusion Mechine	2	P/Day	4,000.00	8,000.00
4	Hire Charge	4	P/Person	1,500.00	6,000.00
5	Mechanic Charge(For Electro-Fusion Charge)	2	Each	2,020.99	4,041.98
6	Service Connection	2	Each	288.00	3012.48
7	Excavation and removal of soft soil (8*0.76*1.72)=10.46cum	10.46	Cum	635.00	3822.7
8	Supply, depositing and compaction of fine sand (FM 0.8) bedding surrounding and above pipe(8*0.76*1.30)-1.88=6.02cum	6.02	Cum	134.00	298.82
9	Back filling by excavated granular soil (7*0.76*0.42)= 2.23 cum	2.23	Cum	1,862.00	7,448.00
10	Hire Charge Of de-Watering Pump	4	P/Day	3,000.00	3,000.00
	Bamboo, Wooden, Planked Rope, G.I Wire for temporary shoring and boxing to the side of the excavation to maintain a safe working environment for anf depths.	1	L/S		
Total					49,723.98


In words: Forty Nine Thousand Seven Hundred Twenty Three Point Nine Eight Tk Only.


০৬/০৮/২০

মোস্তাঈন বিল্লাহ আলমগীর
উপ-সহকারী প্রকৌশলী
মডস জোন-৯
ঢাকা ওয়াসা


০৬/০৮/২০

মোঃ দেলোয়ার হোসেন
সহকারী প্রকৌশলী
মডস জোন-৯
ঢাকা ওয়াসা


০৬.০৮.২০

(মোঃ মোজাহিদুর রহমান)
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডস জোন-৯, ঢাকা ওয়াসা