

Office of the Executive Engineer
MODS Zone-9, Dhaka WASA
Plot # 19, Shajalal Ave. ,Sector # 6, Uttara.


Estimate


Name of work: Repairing of leakage at Rd-35 , Taz Garden House, Sector-7 area under MODS Zone-9, Dhaka WASA.

SL No	Description of the item	Unit	Quantity	Rate(Tk.)	Amount (Tk.)
1	HDPE Pipe 110 mm dia	P/M	3	2024	6072.00
2	HDPE sleeve 110 mm dia	P/Nr	4	1923	7692.00
3	Excavation (8x0.76x1.52)+{3x(1.52x1.52x1.52)}=19.78m ³	19.78	Cum	288.00	5696.64
4	Supply, depositing and compaction of fine sand (FM 0.8) bedding surrounding and above pipe(8*0.76*1.30)-1.88=6.02cum	6.02	Cum	1088.00	6549.76
5	Backfilling 8x0.76x0.91+{3x(1.52x1.52x0.91)}=11.85m ³	11.85	Cum	134.00	1587.90
6	Shifting and connection of existing Service Lines to improve DN 20 to DN 25mm dia	Each	5	1216	6080.00
	Hire charge of E.F machine	P/day	4	1500	6000.00
7	Hire charge of de-watering Pump	P/day	3	1862	5586.00
8	Safety Barriers (Bamboo, Roshi, Plane Sheet, Rent etc)	LS	LS	4000	4000.00
Total					49264.30

In Word : Forty Nine Thousand Two Hundred Sixty Four Point Three Zero Tk only.


 ০৭.০৮.২৩
 Md. Nazmul Hussain
 Sub-Assistant Engineer
 MODS Zone-9
 Dhaka WASA


 ০৭/০৮/২০২৩
 মোঃ ফারুক হোসেন
 সহকারী প্রকৌশলী
 মডুস জোন-৯
 ঢাকা ওয়াসা


 ০৭.০৮.২৩
 (মোঃ মোজাহিদুর রহমান)
 নির্বাহী প্রকৌশলী (চঃ দাঃ)
 মডুস জোন-৯, ঢাকা ওয়াসা