


Office of the Executive Engineer
19, Shahjalal Avenue, Sector #6,
Uttara, Dhaka-1230


Estimate


Name of work: Repairing of leakage at delivery line of 11/B water pump, Sector-11, Uttara under
MODS Zone-9 Dhaka WASA.

SL no.	Description of the Item	Unit	Quantity	Rate(Tk.)	Amount(Tk.)
1	MS Pipe (Normal) 200 mm dia Thickness	P/M	3.5	3068	10738.00
2	Extra-Over item 1 for the supply lay of Ductile/Cast iron/M.S/GI fittings for MS pipes in according with the technical specification M.S Bend 45" dia	P/Nr	1	6545	6545.00
3	MS Dresser coupling 200mm dia	P/Nr	2	1400	2800.00
4	Bedding and surrounding by river saturated Sand. 1x1.82x3.8	Cum	6.92	1088	7528.96
5	Remove of loose soil 1x1.82x3.8	Cum	6.92	288	1992.96
6	Excavation (1.5x1.98x3.8)cum	Cum	11.29	149	1682.21
7	Palisading work by supplying of bitumen drum sheet	sqm	3.5	520	1820.00
8	Delivery line supporting pillar	L.S	2	5000	10000.00
9	Welding charge	L.S	1	5000	5000.00
10	Hire charge of De-watering Pump	P/Day	1	1862	1862.00
				Total(TK)	49969.13

In Word: Forty Nine Thousand Nine Hundred Sixty Nine Point One Three Only.


৯/৬/২৬
মোস্তাঈন বিল্লাহ আলমগীর
উপ-সহকারী প্রকৌশলী
মডুস জোন-৯
ঢাকা ওয়াশা


০২/০৬/২০২৩
মোঃ ফারুক হোসেন
সহকারী প্রকৌশলী
মডুস জোন-৯
ঢাকা ওয়াশা


০৭.০৬.২৩
(মোঃ মোজাহিদুর রহমান)
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডুস জোন-৯, ঢাকা ওয়াশা