



M/S. HOWLADER FOUNDATION

General Marchant *Contractor *Builders *Supplier *Importer & Exporter.



নির্বাহী প্রকৌশলী
মডুস জোন- ৯
ঢাকা ওয়াসা।

তারিখ- ১৪/০৮/২৩ ইং।

বিষয় : Leakage detection and repair-maintenance of 110 mm dia water line at Uttara land office Dalipara, Uttara Dhaka, under MODS Zone-9, Dhaka WASA. কাজের ১ম চলতি ও চূড়ান্ত বিল প্রদান প্রসংগে।

সূত্র: ১। কার্যাদেশ নং-৪৬.০৫.০০০০.৪১৪.২৬.০৬০.২৩-২৫ তারিখ: ২০/০৮/২৩ ইং।

উপরোক্ত বিষয় ও সূত্রের প্রেক্ষিতে জানানো যাচ্ছে যে, Leakage detection and repair-maintenance of 110 mm dia & 160 mm dia water line at Road No-6, Prianka Housing and Road-23 sector-14, under MODS Zone-9, Dhaka WASA. কাজটি নির্ধারিত সময়ের মধ্যে (১৩/০৮/২৩ ইং) সিডিউল মোতাবেক শুষ্ঠভাবে সম্পন্ন করেছি। মোট বিলের পরিমাণ ৮-৪৯,৯১২.৩০/- (উনপঞ্চাশ হাজার নয়শত বার দশমিক তিন শত) টাকা মাত্র।

SI	Description of the item	Quantity	Unit	Rate	Amount
1	Supply & lay unpracticed polyvinyl chloride HDPE Water pipe line in accordance with the technical specification and the standard details drawing of any diameter. All completed as per direction by the engineer.				
	37 mm dia HDPE Pipe	10	Meter	185.001	1850.010
	50 mm dia HDPE Pipe	5	Meter	450.001	2250.005
	110 mm dia HDPE Pipe	1.5	Meter	2,024.001	3036.002
	160 mm dia HDPE Pipe	1	Meter	2,400.960	2400.960
	110 mm dia HDPE Sleeve	2	Each	1,923.001	3846.002
	160 mm dia HDPE Sleeve	2	Each	2,375.000	4750.000
2	Sand filling in foundation trenches.all complete and accepted by the Engineer-in-charge. $(0.9 \times 3 \times 1.5) + (0.8 \times 3 \times 1.5) = 4.05 + 3.6 = 7.65$	7.65	Cum	1,088.001	8323.208
3	Extra -over item I for the excavation and removal of loose soil from site and the back fill of the excess excavation with approved with the technical specification.	7.65	Cum	1,054.001	8063.108
4	Hire Charge of 1.5 KVA mobile Generator.for power supply to drive electrofusion machine. Including fuel and operators all complete as per direction of the E/C.	1	Per/day	2,000.001	2000.001
5	Hire Charge of electrofusion machine to joint sleeve in the excavation. all complete as per direction of the E/C.	1	Per/day	1,500.001	1500.001
6	Hire Charge of de-watering pump.	2	Per/day	1,862.001	3724.002
7	Connection of existing house service line				
	a)DN- 20 to DN 25 mm dia	3	Each	1,216.001	3648.003
	b)DN- 32 to DN 50 mm dia	1	Each	2,021.001	2021.001
8	LS Road Safety measures and tools as per direction of Engineer in Charge	1	Each	2500.001	2500.00
				Total Tk=	49,912.30

In Word- Forty Nine Thousand Nine Hundred Twelve Point Three Zero Taka Only

এমতাবস্থায় আমার দাখিলকৃত আলোচ্য কাজের কার্যসমাপ্তির রিপোর্ট গ্রহন ও ১ম চলতি ও চূড়ান্ত বিল বাবদ সর্বমোট ৮-৪৯,৯১২.৩০/- (উনপঞ্চাশ হাজার নয়শত বার দশমিক তিন শত) টাকা পরিশোধের ব্যবস্থা গ্রহন করতে একান্ত মর্জি হয়।

বিলটি পরীক্ষা করা হয়েছে। পরিমাণ সঠিক আছে। অনুমোদন করা হয়েছে।

28.08.26
Md. Nazmul Hussain
Sub-Assistant Engineer
MODS Zone-9
Dhaka WASA

28/08/2026
মোঃ ফারুক হোসেন
সহকারী প্রকৌশলী
মডুস জোন-৯
ঢাকা ওয়াসা

14.08.23
(মোঃ মোজাহিদুর রহমান)
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডুস জোন-৯, ঢাকা ওয়াসা

M/S. Howlader Foundation

Proprietor