

**OFFICE OF THE EXECUTIVE ENGINEER
MODS ZONE-9, DHAKA WASA**

Estimate

Name of The Work: Interior works of WASA Bill collection room at 1st floor of MODS Zone-9 New office building, Dhaka WASA.


Sl No	Item code	Description	Unit	Quantity	Rate (TK)	Amount (Tk)
1	PDW-22.4	Supplying, fitting and fixing special quality 10 mm thick clear tempered glass door including all accessories, 1 set floor mounted auto door closure, 2 nos. clamping devices, 1 set locking device, top hinge and handle etc. complete in all respect as per drawing and direction of the Engineer-in charge. 3.5x8= 28 sft= 2.60 Sqm	Sqm	2.6	15,816.00	41,121.60
2	21.1.1	Supplying & fixing AC capacitor type ceiling fan (without following regulator) of. specifications and sizes complete with minimum 305 mm (1ft) long and 0.75-1.0" , dia, 2.3 mm thickness MS pipe down rod., temperature cast aluminum blades. 2.5 400V AC capacitor canopy double Z ball bearing, best quality silicon sheet core. Best quality copper made super enamel wire, aluminum alloyed casting body having safety pin with powder coated heat/	Nos	2	3,914.00	7,828.00
3		White cement, Gum, Lump sum	item	1	1,000.00	1,000.00
Total Taka:						49,949.60

In Word-Forty Nine Thousand Nine Hundred Forty Nine Point Six Zero Taka Only


06.08.23

মোঃ নাজমুল হোসাইন
উপ-সহকারী প্রকৌশলী
মডস জোন-৯
ঢাকা ওয়াসা


06/08/23


06.08.2023

(মোঃ মোজাহিদুর রহমান)
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডস জোন-৯, ঢাকা ওয়াসা