

Office Of the Executive Engineer						
Dhaka Water Works, MODS Zone-2, Dhaka WASA						
Subject:Maintenance & servicing of 03(three) sets 37KW 858m3/hr capacity settled water pump motor.						
Priced Bill of Quantities (BOQ) (Form PW2b)						
Sl. No.	Basis of rate	Description of item	Qty	Unit	Unit Rate(Tk.)	Total Amount(Tk)
1	Market price	Disconnection and reconnection of motor terminal box and other electric connection etc by Skilled & Expert foreman/electrician with proper safety maintain.	3	sets	2,500.000	7,500.000
2	Do	Carefully dismantling the delivery pipe line & cleaning by iron paper and fitting-fixing and painting works.	3	Item	2,000.000	6,000.000
3	Do	Cleaning the motor foundation block by skilled labor with jute, petrol etc.	3	Item	1,300.000	3,900.000
4	Do	Withdrawal of submersible pump motor, cable, bend etc. all complete	3	set	978.000	2,934.000
5	Do	Maintenance & servicing of 37KW 858m3/hr capacity submersible by local workshop and engaged skilled & experienced electro-mechanical foreman, mechanics, workers and necessary equipment's, materials like rubber gasket, GM ring, SS stick, nut bolt, washer, MS wheel nut, etc & tools.	3	Each	8,600.000	25,800.000
6	Do	Installation of submersible pump, motor, cable, bend etc. all complete	3	set	943.000	2,829.000
			Sub Total Tk=			48,963.00
Taka In Words : Forty Eight Thousand Nine Hundred Sixty Three Taka only.						

22/03/23
সম্প্রদায় মিয়া
উপ-সহকারী প্রকৌশলী
ঢাকা ওয়াটার ওয়ার্কস
মডস জোন-২, ঢাকা ওয়াসা।

22/03/23
মোঃ আবদুর রব মিয়া
উপ-বিভাগীয় প্রকৌশলী
মডস জোন-২, ঢাকা ওয়াসা।

22/03/23
মোঃ ফিরোজ আলম
নির্বাহী প্রকৌশলী
মডস জোন-২, ঢাকা ওয়াসা।