

M/S MAA BABAR DUA ENTERPRISE**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	None	Repairing of water line leakage for the excavation and removal of soft soil (on written permission of E/C) from the trench bottom beyond allowable depth and back fill of this by supplying, depositing and compaction in 150 mm layer of fine sand (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge,	Cum	311.250	331.001	Three Hundred and Thirty-One point Zero Zero One	103024.061	One Lakh Three Thousand AND Twenty-Four point Zero Six One	I have seen
2	Civil	None	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutchra road surface	Cum	221.250	154.001	One Hundred and Fifty-Four point Zero Zero One	34072.721	Thirty-Four Thousand AND Seventy-Two point Seven Two One	I have seen
3	Civil	None	Repairing of water line leakage for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	Cum	84.000	578.001	Five Hundred and Seventy-Eight point Zero Zero One	48552.084	Forty-Eight Thousand Five Hundred and Fifty-Two point Zero Eight Four	I have seen
4	Civil	None	Extra over item 1 for completing temporary reinstatement of rigid and flexible paved road by compacted sand (FM 1.2) of 75 mm thick and one layer brick soling by full burned 1st class bricks of appropriate size (excavated bricks of proper sizes and quality is allowed to use) of the existing surfaced road in accordance with the technical specification and direction of Engineering in charge, and standard detail drawing for all water pipeline of any diameters for the type of	Sqm.	30.000	74.001	Seventy-Four point Zero Zero One	2220.030	Two Thousand Two Hundred and Twenty point Zero Three	I have seen

			road Surface given below. Asphalt/concrete road surface							
5	Civil	None	Dismantle of R.C.C. Road and Removal of debris to a safe distance	Cum	6.000	2790.001	Two Thousand Seven Hundred and Ninety point Zero Zero One	16740.006	Sixteen Thousand Seven Hundred and Forty point Zero Zero Six	I have seen
6	Civil	None	Shore protection work during excavation in foundation trenches to protect loss due to damage of property by Palisading beyond 1.5 m depth accepted by the Engineer [the rate is including cost of vertical post]	Sqm.	99.000	814.001	Eight Hundred and Fourteen point Zero Zero One	80586.099	Eighty Thousand Five Hundred and Eighty-Six point Zero Nine Nine	I have seen
7	Civil	None	300mm dia CI Dresser-Coupling in/c Nut-bolts	Each	6.000	3019.001	Three Thousand AND Nineteen point Zero Zero One	18114.006	Eighteen Thousand One Hundred and Fourteen point Zero Zero Six	I have seen
8	Civil	None	200mm dia CI Dresser-Coupling in/c Nut-bolts	Each	30.000	1668.001	One Thousand Six Hundred and Sixty-Eight point Zero Zero One	50040.030	Fifty Thousand AND Forty point Zero Three	I have seen
9	Civil	None	150mm dia CI Dresser-Coupling in/c Nut-bolts	Each	20.000	1411.001	One Thousand Four Hundred and Eleven point Zero Zero One	28220.020	Twenty-Eight Thousand Two Hundred and Twenty point Zero Two	I have seen
10	Civil	None	100mm dia CI Dresser-Coupling in/c Nut-bolts	Each	12.000	951.001	Nine Hundred and Fifty-One point Zero Zero One	11412.012	Eleven Thousand Four Hundred and Twelve point Zero One Two	I have seen
11	Civil	None	225X225X225mm Tee	Each	5.000	5345.001	Five Thousand Three Hundred and Forty-Five point Zero Zero One	26725.005	Twenty-Six Thousand Seven Hundred and Twenty-Five point Zero Zero Five	I have seen
12	Civil	None	225X160X225mm Tee	Each	5.000	3900.001	Three Thousand Nine Hundred point Zero Zero One	19500.005	Nineteen Thousand Five Hundred point Zero Zero Five	I have seen

13	Civil	None	160X110X160mm Tee	Each	4.000	2460.001	Two Thousand Four Hundred and Sixty point Zero Zero One	9840.004	Nine Thousand Eight Hundred and Forty point Zero Zero Four	I have seen
14	Civil	None	90° PVC bend 225mm dia	Each	4.000	4888.001	Four Thousand Eight Hundred and Eighty-Eight point Zero Zero One	19552.004	Nineteen Thousand Five Hundred and Fifty-Two point Zero Zero Four	I have seen
15	Civil	None	1 inch Bond Plug/End Cap	Each	120.000	25.001	Twenty-Five point Zero Zero One	3000.120	Three Thousand point One Two	I have seen
16	Civil	None	3/4 inch Bond Plug/End Cap	Each	100.000	20.001	Twenty point Zero Zero One	2000.100	Two Thousand point One	I have seen
17	Civil	None	8 inch Clamp	Each	28.000	500.001	Five Hundred point Zero Zero One	14000.028	Fourteen Thousand point Zero Two Eight	I have seen
18	Civil	None	6 inch Clamp	Each	22.000	350.001	Three Hundred and Fifty point Zero Zero One	7700.022	Seven Thousand Seven Hundred point Zero Two Two	I have seen
							Grand Total:	495298.357	Four Lakh Ninety-Five Thousand Two Hundred and Ninety-Eight point Three Five Seven	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mrs. Salma Sultana on behalf of M/S MAA BABAR DUA ENTERPRISE