


[View All Notifications](#)

Priced Bill of Quantities (BOQ)

Tender/Proposal Document

Tender/Proposal Detail

Tender/Proposal ID : 828040 **Invitation Reference No. :** 46.05.0000.424.37.034.23.79
Closing Date and Time : 08-Jun-2023 14:10 **Opening Date and Time :** 08-Jun-2023 14:10
Procuring Entity : Office of the EE, Field Maintenance Division-2, Dhaka WASA
Brief : Installation of Sub Pump Motor at Replacement/ Re-generation/Re-habilitation/Old DTW Under MODS Circle-2, DWASA
Tender/Proposal Status : **Contract Awarded**

[View Notice](#)

Lot Detail

Lot No. : 46.05.0000.424.37.034.23.79
Lot Description : Installation of Sub Pump Motor at Replacement/ Re-generation/Re-habilitation/Old DTW Under MODS Circle-2, DWASA

Unit Rate Basis

Table Name : Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	A	N/A	Carrying pump motor set including other materials-column pipe, shaft, bend, motor discharge head , clamp, washer, rubber gasket, base plate, tools etc. complete from F.M Division and returning of the rest.	Per trip	50	2025.001	Two Thousand	101250.050	One Lakh One	---
2	A	N/A	Installation of sub pump motor,cable, bend, short piece, etc. all complete.	Each	25	943.001	Nine Hundred	23575.025	Twenty-Three	---
3	A	N/A	Tripod & chain pulley carrying, setting, dismantling & returning	per set	25	1793.001	One Thousand	44825.025	Forty-Four Thousand	---
4	A	N/A	Installation of divisional supplied 8" X 6" MS bend	Each	25	385.001	Three Hundred	9625.025	Nine Thousand	---
5	A	N/A	Fitting-fixing of M.S well cover with cable groove at on the top position of DTW, as per direction of the engineer in charge.	Each	25	360.001	Three Hundred	9000.025	Nine Thousand	---
6	A	N/A	Fitting-fixing of 150 mm dia (6") ms clamp, thickness 16 mm (5/8"), 750 mm (30") long, wide=100mm (4")	Per Pair	25	300.001	Three Hundred	7500.025	Seven Thousand	---
7	A	N/A	Installation of flange ended column pipe for installation of sub pump motor. (25x38 nos=950 pcs column pipe)	Each	950	268.001	Two Hundred	254600.950	Two Lakh Fifty-Four	---
8	A	N/A	Collecting of DTW data such as SWL, TFL, continuity test of pump & pump cable etc as per direction of the engineer in charge.	per site	25	120.001	One Hundred	3000.025	Three Thousand	---
9	A	N/A	Disconnection and reconnection of stater/VFD & other electrical connection etc.	Each	24	1874.001	One Thousand	44976.024	Forty-Four Thousand	---
						Grand Total :		498352.174		