

M/S. RAFEEU ENTERPRISE**Bill of Quantities**

Item No. 1	Group 2	Item Code (if any) 3	Description of Items of Works 4	Measurement Unit 5	Quantity 6	Unit Price In figures (BDT) 7	Unit Price In words (BDT) 8	Total Price in figures (BDT) 9	Total Price In words (BDT) 10
1	-	-	Stripping of unserviceable plaster including racking out joints, Cleaning etc.	P/sqm	258.690	200.000	Two Hundred	51738.000	Fifty-One Thousand Seven Hundred And Thirty-Eight
2	-	-	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	P/sqm	258.690	250.000	Two Hundred And Fifty	64672.500	Sixty-Four Thousand Six Hundred And Seventy-Two Point Five
3	-	-	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) Mass concrete in floor (1:2:4) with cement, brick chips and sand of F.M. 1.2	P/cum	2.090	9000.000	Nine Thousand	18810.000	Eighteen Thousand Eight Hundred And Ten
4	-	-	Interior standard acrylic emulsion paint (plastic or matt finish) of approved best quality and colour delivered from authorized local agent of the manufacturer (Berger	P/sqm	192.040	150.000	One Hundred And Fifty	28806.000	Twenty-Eight Thousand Eight Hundred And Six

			robbialac plastic emulsion/Asian apcolite plastic emulsion or equivalent brand) in a sealed container; applying to interior wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of interior sealer of specified brand on prepared surface; then applying 1 coat of interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of interior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.						
5	-	-	Exterior standard acrylic emulsion paint of approved best quality and color with high performance against dirt picking tendency and efflorosence resistance properties along with water resisting properties and resistance properties against fungi, fading and flaking from authorized local agent of the manufacturer (Berger Weather Coat Antidirt Long Life/ Elite Master Coat/ Asian Apex Ultima or equivalent brand) in a sealed container; applying to exterior surface with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding;	P/sqm	192.040	120.000	One Hundred And Twenty	23044.800	Twenty-Three Thousand And Forty-Four Point Eight

			applying 1 coat of exterior sealer of specified brand on prepared surface; then applying 1 coat of exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.						
6	-	-	On exterior surface applying as per manufacturer instructions 3 coat of weather coat of approved quality and colour delivered from authorized local agent of the manufacturer in a sealed container complete in all respect in all floors and accepted by the Engineer.	P/sqm	237.590	120.000	One Hundred And Twenty	28510.800	Twenty-Eight Thousand Five Hundred And Ten Point Eight
7	-	-	Cleaing sludges & night soil from septic tank removing to a safe place/distance without affecting environment. 10 user septic tank	Each	2.000	15000.000	Fifteen Thousand	30000.000	Thirty Thousand
8	-	-	Surface channel wiring for the following point looping at the switch board with earth terminal with 1C-2x1.5 sqmm PVC insulated and sheathed stranded cable (BYM) and same size PVC insulated ECC(BYA) (Green / White Color) including circuit wiring with 1C-2x2.5 sqmm PVC insulated and sheathed stranded cable (BYM) & same size PVC insulated ECC(BYA) Green / White color through minimum 1 mm thick PVC channel complete with 18 SWG GP sheet / PVC switch board (preferably concealed) with 3mm thick ebonite sheet cover, circular box, without switch, fixing materials,	P/point	3.000	8000.000	Eight Thousand	24000.000	Twenty-Four Thousand

			other accessories etc. as required and mending the damages good. All electrical contacts shall be of brass / copper connected through connector or soldering (no twisting shall be allowed) and cables shall be manufactured and tested according to relevant IEC / BDS / BS / VDE standards and as per detailed specification mentioned in Annexure-1. The work shall be carried out as per direction & approval of the Engineer. Light / Fan/exhaust or wall bracket fan point						
9	-	-	Standard synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in sealed container having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brush / roller/spray in 2 coats over single coat anticorrosive coating including cleaning. drying. making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer in charge	P/sqm	164.760	130.000	One Hundred And Thirty	21418.800	Twenty-One Thousand Four Hundred And Eighteen Point Eight
10	-	-	Site cleaning work for removing all debris from the site with contractor own all complete as per Direction of the Engineer in Charge.	P/No	1.000	6000.000	Six Thousand	6000.000	Six Thousand
							Grand Total:	297000.900	Two Lakh Ninety-Seven Thousand Point Nine

This Bill of Quantities is Electronically Signed by Mr. MD NURE SIDDIQUE on behalf of M/S. RAFEEU ENTERPRISE