


[View All Notifications](#)

Priced Bill of Quantities (BOQ)

Tender/Proposal Document

Tender/Proposal Detail

Tender/Proposal ID :	862611	Invitation Reference No. :	46.05.0000.424.37.108.23.29
Closing Date and Time :	31-Aug-2023 14:35	Opening Date and Time :	31-Aug-2023 14:35
Procuring Entity :	Office of the EE, Field Maintenance Division-2, Dhaka WASA		
Brief :	Changing of DOFC & LA complete set with proper wiring at different pump station under MODS Zone- 4 and 10, DWASA.		
Tender/Proposal Status :	Contract Awarded		

[View Notice](#)

Lot Detail

Lot No. :	46.05.0000.424.37.108.23.29
Lot Description :	Changing of DOFC & LA complete set with proper wiring at different pump station under MODS Zone- 4 and 10, DWASA.

Unit Rate Basis

Table Name : Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	A	N/A	Supply and installation of outdoor type 11KV, 50 Hz, 5KA (20 KA) Dropout fuse complete with mounting accessories etc. Made in Bangladesh/ Brazil/ UK/USA countries or equivalent. (3 Nos. in a set).	Each Set	10	25154.001	Twenty-Five	251540.010	Two Lakh Fifty-One	--- v
2	A	N/A	Supply and installation of outdoor type 11 KV, 50 Hz, 100A, (10 KA), 75 KV BIL- Lightning arrester complete with mounting accessories etc. Made in Bangladesh/ Brazil/ UK/USA countries or equivalent. (3 Nos. in a set).	Each Set	5	19019.001	Nineteen	95095.005	Ninety-Five	--- v
3	A	N/A	Providing and fixing of HDBC wire for Lightning arrester Earthing. (5 side x 10 meter=50meter)	Per meter	50	850.001	Eight Hundred	42500.050	Forty-Two	--- v
4	A	N/A	Providing and fixing of 95 mm cable socket copper made.	Each	75	145.001	One Hundred	10875.075	Ten Thousand	--- v
5	A	N/A	Insulation, testing and commissioning of 415V, 3 phase 50 Hz LT switchgear/ VFD/ PFI plant suitable for following capacity Transformer on prepared c.c foundation with the help of necessary tools and plants, skill labour & technician as per direction of the Engineer-in-charge. For 200 KVA transformer	per job	25	3803.001	Three Thousand	95075.025	Ninety-Five	--- v
6	A	N/A	Providing and fixing of 12.5mm inner dia & 2.65mm thickness GI pipe for Lightning arrester Earthing Purpose (5 side x 3 meter long=15 meter)	Per meter	15	223.041	Two Hundred	3345.615	Three Thousand	--- v
							Grand Total :	498430.78		