


নির্বাহী প্রকৌশলীর কার্যালয়

মডস জোন-৫, ঢাকা ওয়াসা।

বিষয়: মডস জোন-৫ এর আওতাধীন ডিএমএ-৫১০ এর মহাখালী এসকেএস টাওয়ারের সামনের ইন্টার ডিএমএ চেম্বার রাইজিং, ক্রিনিং এবং কভার প্রতিস্থাপন করণ কাজ।

SL No	Description of item	Qty	Unit	Rate	Amount
1	Reinforced cement concrete works using wooden shutter, with minimum cement content relates to mix ratio 1:2:4 having minimum $f_{cr} = 24$ Mpa, and satisfying a specified compressive strength $f_{c'} = 19$ Mpa at 28 days on standard cylinders as per standard practice of Code ACI/BNBC/ASTM & cement conforming to BDS EN-197-1- CEM 1, 52.5N (52.5MPa) / ASTM-C 150 Type I, best quality sand [50% quantity of best local sand (F.M. 1.2) and 50% quantity of Sylhet sand or coarse sand of equivalent F.M. 2.2] and 20 mm down well graded picked jhama brick chips conforming ASTM C-33 including breaking chips and screening, making, placing shutter in position and maintaining true to plumb, making shutter water-tight properly, placing reinforcement in position; mixing in standard mixer machine with hopper fed by standard measuring boxes, casting in forms, compacting by vibrator machine and curing at least for 28 days, removing centering-shuttering after specified time approved; including cost of water, electricity, additional testing charges of materials and cylinders required by engineer, other charges etc. all complete approved and accepted by the Engineer.(Rate is excluding the cost of reinforcement and its fabrication, placing and binding etc)	4.5	Cum	7319	32935.50
2	Sand filling in foundation trenches and plinth with coarse sand having min F.M 1.2 in 150mm in layers including leveling, watering and compaction to achieve minimum dry density of 90% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only etc. all complete and accepted by the engineer.	2	Cum	497	994.00
3	Labor for earth excavation to rise Inter DMA Chamber in Road level and back filling of sand and DMA Chamber and operation.	10	person	647	6470.00
4	Purchase for bamboo, rope, hacksaw set, GI wire etc.	1	Lumpsum	1500	1500.00
5	Baricading for safety, Transport and others	2	Lumpsum	3500	7000.00
				Total Tk.	48,899.50
In Word : Forty Eight thousand Eight Hundred Ninety Nine point Five zero only.					


20106126


20106126

মোঃ বাবুল হোসেন
উপ-সহকারী প্রকৌশলী
মডস জোন-৫
ঢাকা ওয়াসা।

মোহাম্মদ আবু ইউসুফ
সহকারী প্রকৌশলী
মডস জোন-৫
ঢাকা ওয়াসা।


21-06-2023
মোহাম্মদ তৌহিদ এলাহী
নির্বাহী প্রকৌশলী (চ: দা:)
মডস জোন-৫ ঢাকা ওয়াসা