


[View All Notifications](#)

Priced Bill of Quantities (BOQ)

Tender/Proposal Document

Tender/Proposal Detail

Tender/Proposal ID :	860797	Invitation Reference No. :	46.05.0000.424.37.093.23.22
Closing Date and Time :	31-Aug-2023 14:00	Opening Date and Time :	31-Aug-2023 14:00
Procuring Entity :	Office of the EE, Field Maintenance Division-2, Dhaka WASA		
Brief :	Rising of Electric Transformer C.C pad with necessary construction works at different pump station under MODS Zone - 4 and 10, DWASA		
Tender/Proposal Status :	Contract Awarded		

[View Notice](#)

Lot Detail

Lot No. :	46.05.0000.424.37.093.23.22
Lot Description :	Rising of Electric Transformer C.C pd with necessary construction works at different pump station under MODS Zone - 4 and 10, DWASA.

Unit Rate Basis

Table Name : Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	A	NA	Removal of sub station fencing net and Installation after completion of Transformer base rising. (two times).	Each site	20	2300.001	Two Thousand	46000.020	Forty-Six Thousand	---
2	A	NA	Cutting, Removing of all types of trees & others from inside the sub station fencing by expert & skill technician. Always ensure the safety & security of the technician.	Each	20	1500.001	One Thousand	30000.020	Thirty Thousand	---
3	A	NA	Construction the temporary CC Pad for shifting the transformer. (As per annexure sheet-1)	Each	3	4910.341	Four Thousand	14731.023	Fourteen Thousand	---
4	A	NA	Disconnection of H.T cable and withdrawn from the ground & Reconnection after prepared the Transformer base(C C PAD).	Each time	20	885.001	Eight Hundred	17700.020	Seventeen Thousand	---
5	A	NA	Disconnection & Reconnection of Existing earthing system.	Each	20	700.001	Seven Hundred	14000.020	Fourteen Thousand	---
6	A	NA	Shifting of the Transformer to the temporary C.C Pad and replacing to the permanent C.C Pad with taking proper safety precautions per job.	Each	20	1650.001	One Thousand	33000.020	Thirty-Three Thousand	---
7	A	NA	Re-construction of existing Permanent CC Pad by using brick, brick chips, sand, cement etc to shifting of the transformer (As per annexure sheet-2)	Each	20	8579.641	Eight Thousand	171592.820	One Lakh Seventy-	---
8	A	NA	Tripod & chain pulley carrying , setting, dismantling and returning.	Each	20	1793.001	One Thousand	35860.020	Thirty-Five Thousand	---
9	A	NA	Installation, testing and commissioning of 11 KV/.415 KV Transformer on prepared platform C.C. foundation with the help of necessary tools & plants. Skilled labour & technician as per direction of the Engineer-in-charge.	Each	20	6749.001	Six Thousand	134980.020	One Lakh Thirty-	---
						Grand Total :		497863.983		

