

NURJAHAN ENTERPRISE**Price and Delivery Schedule for Goods (Form e-PG2-2A)**

Price and Delivery Schedule for Goods

Item No.	Description of Item	Measurement Unit	Quantity	Point of Delivery	Delivery Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Supply of (DN-250, PN-10) Butterfly Valve (ISO Distributor). Model: D34 X-10, with flange adaptor as per given technical specifications (Annex-i)	Each	2.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	245000.001	Two Lakh Forty-Five Thousand point Zero Zero One	490000.002	Four Lakh Ninety Thousand point Zero Zero Two
2	Supply of special type dia MS Redusser in/c nut-bolts with water line. Size: 400x300 mm dia (12 mm thick X 300 mm) as per sample & according to the instructions of engineering in charge	Each	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	35000.001	Thirty-Five Thousand point Zero Zero One	35000.001	Thirty-Five Thousand point Zero Zero One
3	Supply of special type M.S Flange adopter in/c nut-bolts with water line. Size: 400 mm dia X 12 mm as per sample & according to the instructions of engineering in charge	Each	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	28000.001	Twenty-Eight Thousand point Zero Zero One	28000.001	Twenty-Eight Thousand point Zero Zero One
4	Supply of special type M.S Flange adopter in/c nut-bolts with water line.	Each	7.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	24000.001	Twenty-Four Thousand point Zero Zero One	168000.007	One Lakh Sixty-Eight Thousand point

7/18/23, 11:59 AM

View Form

Zero Zero
Seven

	Size: 300 mm dia X 12 mm as per sample & according to the instructions of engineering in charge									
5	Supply of special type dia MS Bend with necessary rubber gasket for SWTP water line. Size: 300x90 mm (12 X 300) mm as per sample & according to the instructions of engineering in charge.	Each	3.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	30000.001	Thirty Thousand point Zero Zero One	90000.003	Ninety Thousand point Zero Zero Three
6	Supply of special type dia MS Redusser in/c nut-bolts with water line. Size: 300x250 mm dia (12 mm thick X 300 mm) as per sample & according to the instructions of engineering in charge	Each	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	25000.001	Twenty-Five Thousand point Zero Zero One	25000.001	Twenty-Five Thousand point Zero Zero One
7	Control and telemetry unit set (RTU).	Each	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	695000.001	Six Lakh Ninety-Five Thousand point Zero Zero One	695000.001	Six Lakh Ninety-Five Thousand point Zero Zero One
								Grand Total:	1531000.016	Fifteen Lakh Thirty-One Thousand point Zero One Six

This Price and Delivery Schedule for Goods (Form e-PG2-2A) is Electronically Signed by Mr. Md. Shariful Islam on behalf of NURJAHAN ENTERPRISE

NURJAHAN ENTERPRISE

Price and Completion Schedule for Related Services (Form e- PG2-2B)

Price and Completion Schedule for Related Services

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Installation and laying of Ductile cast Iron Pipe(DI) water pipelines by Open Cut method in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. The rate includes for excavation in all kinds of soil,BFS/HBB/Bituminous road/Cement Concrete/Reinforced Cement Concrete road surface except rock to the full depth of trench required by the specifications, precautions necessary to avoid damage of underground utility services, (if any damage occurs, Contractor shall repair by his own cost) including removing the excavated earth & stacking the same to safe distance without any traffic obstacles, de-watering of the trench to keep dry condition at all times, including all necessary shoring, boxing, must be protected from any collapse of trench sides, transportation of pipes to site, cleaning, jointing and laying of the water pipes; disposal of surplus excavated material and transport back surplus materials to Dhaka WASA stores, as per specifications and direction of Engineering in charge (As per given detailed Estimates & technical specification Annex-ii)	job	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	70000.001	Seventy Thousand point Zero Zero One	70000.001	Seventy Thousand point Zero Zero One
2	Construction of RCC chamber of dimension 3600x2100x3000mm with slab thickness 300 mm including climbing ladder (MHC will be supplied from the store of SWTP (As per given drawing, Calculation, Estimate and technical specification.-Annex-iii)	each	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	335000.001	Three Lakh Thirty-Five Thousand point Zero Zero One	335000.001	Three Lakh Thirty-Five Thousand point Zero Zero One

3	Installation & Commissioning of e-PRV & Flowmeter, RTU unit, SCADA Software inside the chamber and Modification of the existing transmission line inside the chamber as per direction of engineer in charge.	each	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	Asper Document enclosed	10000.001	Ten Thousand point Zero Zero One	10000.001	Ten Thousand point Zero Zero One
								Grand Total:	415000.003	Four Lakh Fifteen Thousand point Zero Zero Three

This Price and Completion Schedule for Related Services (Form e- PG2-2B) is Electronically Signed by Mr. Md. Shariful Islam on behalf of NURJAHAN ENTERPRISE