

RS Technocracy

Price and Delivery Schedule for Goods (Form e-PG2-2A)

Price and Delivery Schedule for Goods

Item No.	Description of Item	Measurement Unit	Quantity	Point of Delivery	Delivery Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Supply of tap of box with TPMCCB of 500 A ratings.	each	1.000	PSTP Divisional store	60	China	15000.001	Fifteen Thousand point Zero Zero One	15000.001	Fifteen Thousand point Zero Zero One
2	Supply of Copper bar (size-305 mm x 75 mm x 5 mm)	each	1.000	PSTP Divisional store	60	BD	1500.001	One Thousand Five Hundred point Zero Zero One	1500.001	One Thousand Five Hundred point Zero Zero One
3	Supply of 1C - 4 x 50 sqmm (NYY).	meter	20.000	PSTP Divisional store	60	BD	4700.001	Four Thousand Seven Hundred point Zero Zero One	94000.020	Ninety-Four Thousand point Zero Two
4	Supply of 1C - 4 x 35 sqmm (NYY).	meter	12.000	PSTP Divisional store	60	BD	3700.001	Three Thousand Seven Hundred point Zero Zero One	44400.012	Forty-Four Thousand Four Hundred point Zero One Two
5	Supply of 200/5 LTCT	each	3.000	PSTP Divisional store	60	China	1200.001	One Thousand Two Hundred point Zero Zero One	3600.003	Three Thousand Six Hundred point Zero Zero Three
6	Supply of (50A-200A) cable lugs	pack	5.000	PSTP Divisional store	60	BD	600.001	Six Hundred point Zero Zero One	3000.005	Three Thousand point Zero Zero Five
7	Supply of (35A-45A) cable lugs	pack	5.000	PSTP Divisional store	60	BD	900.001	Nine Hundred point Zero Zero One	4500.005	Four Thousand Five Hundred point Zero Zero Five
8	Supply of PVC pipe minimum inner dia 75 mm & minimum wall thickness 3	meter	10.000	PSTP Divisional store	60	BD	150.001	One Hundred and Fifty point Zero Zero One	1500.010	One Thousand Five Hundred point Zero One

9	Supply of PVC pipe minimum inner dia 50 mm & minimum wall thickness 2.5 mm.	meter	10.000	PSTP Divisional store	60	BD	120.001	One Hundred and Twenty point Zero Zero One	1200.010	One Thousand Two Hundred point Zero One
10	"Supply of 100A TPDB Incoming : 1x100A TPMCCB (10 KA) Outgoing: 6x10-20A TPMCCB (10 KA)"	each	3.000	PSTP Divisional store	60	Italy	15000.001	Fifteen Thousand point Zero Zero One	45000.003	Forty-Five Thousand point Zero Zero Three
11	"Supply of 200A TPDB Incoming : 1x200A TPMCCB (16 KA) Outgoing: 10x10-30A TPMCCB (10 KA)"	each	1.000	PSTP Divisional store	60	Italy	22000.001	Twenty-Two Thousand point Zero Zero One	22000.001	Twenty-Two Thousand point Zero Zero One
12	Supply of Tap of box with TPMCCB of (16 A - 100 A) ratings.	each	3.000	PSTP Divisional store	60	China	7000.001	Seven Thousand point Zero Zero One	21000.003	Twenty-One Thousand point Zero Zero Three
13	Supply of Tap of box with TPMCCB of (125 A - 160 A) ratings.	each	1.000	PSTP Divisional store	60	China	9000.001	Nine Thousand point Zero Zero One	9000.001	Nine Thousand point Zero Zero One
14	Supply of Tap of box with TPMCCB of (200 A - 250 A) ratings.	each	2.000	PSTP Divisional store	60	China	15000.001	Fifteen Thousand point Zero Zero One	30000.002	Thirty Thousand point Zero Zero Two
15	Supply of PVC pipe minimum inner dia 40 mm & minimum wall thickness 2.2 mm.	meter	30.000	PSTP Divisional store	60	BD	120.001	One Hundred and Twenty point Zero Zero One	3600.030	Three Thousand Six Hundred point Zero Three
16	Supply and fixing of copper made sockets / ferules for following size cables 35 sqmm	each	50.000	PSTP Divisional store	60	BD	390.001	Three Hundred and Ninety point Zero Zero One	19500.050	Nineteen Thousand Five Hundred point Zero Five
17	Supply of Distribution PVC box	each	2.000	PSTP Divisional store	60	BD	5500.001	Five Thousand Five Hundred	11000.002	Eleven Thousand point Zero Zero

								Zero Zero One		
18	Supply of 1C-2x10 sqmm (BYM) cable with 10 sqmm (BYA) ECC wire	meter	41.000	PSTP Divisional store	60	BD	900.001	Nine Hundred point Zero Zero One	36900.041	Thirty-Six Thousand Nine Hundred point Zero Four One
19	Supply of 1C-2x16 sqmm (BYM) cable with 16 sqmm (BYA) ECC wire through PVC pipe of minimum inner dia 40 mm having wall thickness of 2.2 mm	meter	75.000	PSTP Divisional store	60	BD	900.001	Nine Hundred point Zero Zero One	67500.075	Sixty-Seven Thousand Five Hundred point Zero Seven Five
20	Supply of PVC pipe minimum inner dia 20 mm & minimum wall thickness 1.5 mm.	meter	12.000	PSTP Divisional store	60	BD	110.001	One Hundred and Ten point Zero Zero One	1320.012	One Thousand Three Hundred and Twenty point Zero One Two
21	Supply of 1C-2x2.5 sqmm (BYM) cable with 2.5 sqmm (BYA) ECC wire through PVC pipe of minimum inner dia 25 mm having wall thickness of 1.5 mm	meter	30.000	PSTP Divisional store	60	BD	190.001	One Hundred and Ninety point Zero Zero One	5700.030	Five Thousand Seven Hundred point Zero Three
22	Supply of 100W led metal light Gloria cat no-GLFL-902. Energy cat no-EPFDL-17001/100 W. Cosmo cat no-BDTCL-LEDI-02. Adex-ADFLE-100 W830. Asha cat no-ACS-LEL-2155 N(100 W) or equivalent.	each	2.000	PSTP Divisional store	60	China	4500.001	Four Thousand Five Hundred point Zero Zero One	9000.002	Nine Thousand point Zero Zero Two
23	Supply of 200W led metal light	each	16.000	PSTP Divisional store	60	China	8500.001	Eight Thousand Five	136000.016	One Lakh Thirty-Six Thousand

	Energy cat no-EPFDL-17011/200 W. Cosmo cat no-BDTCL-LEDI-03 Adex-ADFLE-200W865. Asha cat no-CFLD-024-200w. CFLD-024-200W or equivalent.							Zero Zero One		Zero One Six
24	Supply of 400W led metal light. Gloria cat no-GLFL-915. Energy cat no-EPFDL-17013/400 W. Adex-ADFLE-420W840. Asha cat no-CFLD-024-400W. Crescent cat no-CFLD-024-400W or equivalent.	each	2.000	PSTP Divisional store	60	China	20000.001	Twenty Thousand point Zero Zero One	40000.002	Forty Thousand point Zero Zero Two
25	1C-4x16 sqmm (NYY) with 16 sqmm (BYA) ECC wire through PVC pipe of minimum inner dia 40 mm having wall thickness of 2.2 mm	meter	238.000	PSTP Divisional store	60	BD	1000.001	One Thousand point Zero Zero One	238000.238	Two Lakh Thirty-Eight Thousand point Two Three Eight
26	1C-4x10 sqmm (NYY) with 10 sqmm (BYA) ECC wire through PVC pipe of minimum inner dia 40 mm having wall thickness of 2.2 mm	meter	272.000	PSTP Divisional store	60	BD	1300.001	One Thousand Three Hundred point Zero Zero One	353600.272	Three Lakh Fifty-Three Thousand Six Hundred point Two Seven Two
27	"Supply of Motion Sensor Light (200 W) Specification: Type: Motion Sensor Light Switch Mode Setting: Deep Dark / Light Dark /	each	16.000	PSTP Divisional store	60	China	15500.001	Fifteen Thousand Five Hundred point Zero Zero One	248000.016	Two Lakh Forty-Eight Thousand point Zero One Six

	Time Delay: 15Secs / 45Secs / 5Min Detection Range: 4-6m Detection Angle: 110degree Working Voltage: AC100-240V, 50/60Hz Color: White"									
28	Supply of PVC pipe minimum inner dia 100 mm & minimum wall thickness 3.4mm	meter	8.000	PSTP Divisional store	60	BD	400.001	Four Hundred point Zero Zero One	3200.008	Three Thousand Two Hundred point Zero Zero Eight
29	Supply of PVC pipe minimum inner dia 30 mm & minimum wall thickness 1.9 mm.	meter	120.000	PSTP Divisional store	60	BD	250.001	Two Hundred and Fifty point Zero Zero One	30000.120	Thirty Thousand point One Two
								Grand Total:	1499020.991	Fourteen Lakh Ninety- Nine Thousand AND Twenty point Nine Nine One

This Price and Delivery Schedule for Goods (Form e-PG2-2A) is Electronically Signed by Mr. Md. Haque on behalf of RS Technocracy

RS Technocracy

Price and Completion Schedule for Related Services (Form e- PG2-2B)

Price and Completion Schedule for Related Services

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	Providing and fixing of 1524 mm (5') long 38.1 mm (1.5") dia GI. pipe service bracket complete with 1 no. of GI bend 2 nos. fixing clamps of 38.10 mm x 6.35 mm (1.5" x 1/4") size iron flat bar bolts, nuts etc. complete as required.	job	1.000	PSTP Compound	60	BD	30000.001	Thirty Thousand point Zero Zero One	30000.001	Thirty Thousand point Zero Zero One
2	Providing and fixing standard service clamp for jointing service cable with the overhead conductor complete as required	set	100.000	PSTP Compound	60	BD	450.001	Four Hundred and Fifty point Zero Zero One	45000.100	Forty-Five Thousand point One
3	Providing and fixing of depth of bottom of main electrode at 6858 mm. (22.5 ft) from GL & length of electrode 6096 mm. (20 ft).	job	1.000	PSTP Compound	60	BD	32000.001	Thirty-Two Thousand point Zero Zero One	32000.001	Thirty-Two Thousand point Zero Zero One
4	Providing and fixing of surface / concealed type self-extinguishing PVC board of 76.2 mm(3") depth (with open front) duly painted inner & outer surfaces with anchoring arrangement to be fitted in wall (only back surface of the board will be considered for measurement).	sqm	2.000	PSTP Compound	60	BD	15000.001	Fifteen Thousand point Zero Zero One	30000.002	Thirty Thousand point Zero Zero Two
5	Providing and fixing of almirah type 18 SWG metal board of depth 228mm (6") duly painted with powder coating with epoxy polyester resin on all	sqm	2.800	PSTP Compound	60	BD	18000.001	Eighteen Thousand point Zero Zero One	50400.003	Fifty Thousand Four Hundred point Zero Zero Three

	having built in push type / suitable locking arrangement including metal bridges of suitable size for fixing of all electrical control devices complete with suitable anchoring arrangement in wall / column and keeping provision With water tight arrangement.									
6	Providing and fixing of copper flat bar (5 nos) : 4 nos 18"x1.5"x10mm and 1 no 4"x1.5"x10mm for earthing mounted on insulator at both ends individually.	each	1.000	PSTP Compound	60	BD	1600.001	One Thousand Six Hundred point Zero Zero One	1600.001	One Thousand Six Hundred point Zero Zero One
7	Providing and fixing of SS base plate (dia-6 inch, theckness-4mm) with u-clump and nut bolt.	each	8.000	PSTP Compound	60	BD	15000.001	Fifteen Thousand point Zero Zero One	120000.008	One Lakh Twenty Thousand point Zero Zero Eight
8	Making following cable trench in pucca floor having 76.2 mm (3") thick CC (4:2:1) base on one layer of flat brick soling over 76.2 mm (3") thick sand bedding at the bottom, 127 mm (5") thick brick work (4:1) at the sides complete with 12.7 mm (1/2") plaster and neat cement finishing duly covered with 4.8 mm (3/16") thick MS sheet having necessary lifting lugs : W (width) ? 457 mm x D (depth) ? 864 mm	meter	12.000	PSTP Compound	60	BD	5500.001	Five Thousand Five Hundred point Zero Zero One	66000.012	Sixty-Six Thousand point Zero One Two
9	Stripping of unserviceable plaster including racking out joints, cleaning etc.	sqm	192.000	PSTP Compound	60	BD	440.001	Four Hundred and Forty point Zero Zero One	84480.192	Eighty-Four Thousand Four Hundred and Eighty point One Nine Two
10	Hire charge of suspended scaffolding (gondula) made	days	8.000	PSTP Compound	60	BD	6000.001	Six Thousand point Zero Zero One	48000.008	Forty-Eight Thousand point Zero Zero One

11	25 mm thick artificial patent stone (1:2:4) flooring with cement, best quality coarse sand (50% quantity of Sylhet sand or coarse sand of equivalent F.M. 2.2 and 50% best quality local sand of FM 1.2) and 12 mm down well graded stone chips, laying the concrete in alternate panels, compacting and finishing the top with neat cement and curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) In ground floor	sqm	192.000	PSTP Compound	60	BD	590.001	Five Hundred and Ninety point Zero Zero One	113280.192	One Lakh Thirteen Thousand Two Hundred and Eighty point One Nine Two
12	Approved best quality and colour synthetic polyvinyl distemper delivered from authorized local agent of the manufacturer in a sealed container, applying to wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of interior sealer of specified brand on prepared surface; then applying 1 coat of interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand	sqm	192.000	PSTP Compound	60	BD	460.001	Four Hundred and Sixty point Zero Zero One	88320.192	Eighty-Eight Thousand Three Hundred and Twenty point One Nine Two

	of synthetic polyvinyl distemper spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.									
13	All working site cleaning.	item	1.000	PSTP Compound	60	BD	28000.001	Twenty-Eight Thousand point Zero Zero One	28000.001	Twenty-Eight Thousand point Zero Zero One
								Grand Total:	737080.713	Seven Lakh Thirty-Seven Thousand AND Eighty point Seven One Three

This Price and Completion Schedule for Related Services (Form e- PG2-2B) is Electronically Signed by Mr. Md. Haque on behalf of RS Technocracy