



M/S. MITHU & BROTHERS

1st Class Contractor & Supplier

135/4 South Chayabithy, Joydebpur, Gazipur.

Mobile : 01915-789016, Email: mithu&brothers1965@gmail.com

OFFICE OF THE EXECUTIVE ENGINEER

MODS ZONE-9, DHAKA WASA

Ref: Name of the work: Installation and repair-maintenance of different dia sluice valve at DMA-905.....
DMA-906 under MODS Zone-9, Dhaka WASA

Sl no	Rate schedule Item No.	Description of Materials	Quantity	Unit	Rate	Amount
1	PWD-2.1.2	Earth work in road embankment up to a lift of 1.5 m in all kinds of soil including cutting and throwing earth in layers not exceeding 150 mm in thickness, breaking clods up to 40 mm size in each layer, ramming, leveling and dressing as per required side slope and alignment with earth borrowed from the road side govt. acquired land for any leads and maintaining the embankment true to level and side slopes as per profiles for one year from the date of completion including making dug, bailing, profiling etc. complete and accepted by the Engineer-in-charge.	6.80	Cum	168.001	1,142.407
2	WASA1/3/b	6" C class PVC pipe for fitting and fixing in S/V and ashout chamber, all completed as per direction of Engineer in arge.	14.00	RM	805.001	11,270.014
3	PWD-2.9	Extra -over item 1 for the excavation and removal of loose soil from site and the back fill of the excess excavation with approved with the technical specification .	6.80	Cum	1,054.001	7,167.207
4	Approved Rate	Repair and Maintenance & Construction work of various diameter sluice valve. Sluice valve spindle, pinium, gate, nut volt open from the s/v chamber and repair/ reconstruction from workshoop. Then fitting and fixing with s/V and replace into the chamber. Materials cost labour charge caring charge all included in unit rate. All completed as per direction by the engineer.				
a		300 mm dia SV spindle	2.00	Each	5,000.001	10,000.002
5		200 mm dia SV spindle	6.00	Each	4,000.001	24,000.006
6		150 mm dia SV spindle	8.00	Each	3,500.001	28,000.008
7		100 mm dia SV spindle	8.00	Each	3,000.001	24,000.008
8		300 mm dia SV Pinium	2.00	Each	3,500.001	7,000.002
9		200 mm dia SV Pinium	6.00	Each	2,500.001	15,000.006
10		150 mm dia SV Pinium	8.00	Each	2,000.001	16,000.008
11		110 mm dia SV Pinium	8.00	Each	1,500.001	12,000.008
12		Nut volt	70.00	Each	80.001	5,600.070
13		Gate	80.00	Each	90.001	7,200.080
14	Approved rate	Extra -over item 1 for supply and lay of HDPE sleeve for the pipe materials and diameter given below in accordance with the technical specification and the standard detail drawing.				
		200 mm dia E.F Sleeve	2	Each	2,537.001	5,074.002
15		160 mm dia E.F Sleeve	6	Each	1,595.001	9,570.006



M/S. MITHU & BROTHERS

1st Class Contractor & Supplier

135/4 South Chayabithy, Joydebpur, Gazipur.

Mobile: 01915-789015, E-mail: mithu&brothers1965@gmail.com

17		110 mm dia. 8" Sleeves				6632.008
17	PWD-	Sand filling in foundation trenches and plinth with sand having				
Ref:	02.10.1	F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per esign supplied by the design office only, all complete and accepted by the Engineer-in-charge.	7.09	Cum	Date: 1,088.001	7,713.927
18	WASA R.S-18	Hire Charge of de-watering pump. Bailing out of all from pipe line trench with supply of De- watering pump required size including supplying of fuel, lubricants and all other required accessories & manpower to keep the trench in a dry condition at all times etc. all complete as per direction of the E/C.	15	Per/day	1,862.001	27,930.015
19	PWD-24.10	Providing compacted sub-base course with well graded material of crushed well burnt picked jhama / 1st class brick bats and sand (FM 0.8) with mixing proportion 2 : 1 having compacted thickness made as per specification including local handling, spreading uniformly to proper grade camber and super elevation, packing, rolling properly with 8 to 10 ton capacity power driven road roller and watering properly for compaction of 100% MDD (standard) blinding with sand including cost of fuel, lubricants, spares, maintenance, driver etc. all complete and accepted by the Engineer-in-charge.	12.52	Sqm	5449.001	68,221.493
20		Road Safety measures and tools as per direction of Engineer in	1	L.S	4,999.999	4,999.999
Sub Total						298,521.275
Deduction of 5% les Amount						-14,926.060
Net Payable Amount of Tk=						283,595.215
In word: Two Lac Eighty Three Thousand Five Hundred Ninety Five Point Two One Five Taka Only.						

খিলটি পরীক্ষা করা হয়েছে। পরিমাণ ঠিক আছে। Payment Invoice চি
অনুমোদন করা যাবে।

08.08.23
Md. Nazmul Hussain
Sub-Assistant Engineer
MODS Zone-9
Dhaka WASA

08/08/2023
মোঃ ফারুক হোসেন
সহকারী প্রকৌশলী
মডস জোন-৯
ঢাকা ওয়াসা

স্বাক্ষরিত
08.08.23
(মোঃ মোজাহিদুর রহমান)
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডস জোন-৯, ঢাকা ওয়াসা:

(M/S. MITHU & BROTHERS)
PROPRIETOR



M/S. MITHU & BROTHERS

1st Class Contractor & Supplier

135/4 South Chayabithy, Joydebpur, Gazipur.

Mobile : 01915-789015, E-mail : mithu&brothers1965@gmail.com

Ref:



Date : ৭. ০৮. ২০২৩

নির্বাহী প্রকৌশলী
মড্‌স জোন- ৯
ঢাকা ওয়াসা।

তারিখ- ০৭/০৮/২০২৩ ইং।

বিষয় : Installation and repair-maintenance of different dia sluice valve at DMA-905 DMA-906 under MODS Zone-9, Dhaka WASA কাজের ১ম চলতি ও চূড়ান্ত বিল প্রদান প্রসঙ্গে।

সূত্র: ১। কার্যাদেশ নং-৪৬.০৫.০০০০.৪১৪.২৬.০৫১.২২-৩৯

তারিখ : ০৪/০৬/২০২৩ ইং।

e-GP Tender ID-744449

উপরোক্ত বিষয় ও সূত্রের প্রেক্ষিতে জানানো যাচ্ছে যে, Installation and repair-maintenance of different dia sluice valve at DMA-905 DMA-906 under MODS Zone-9, Dhaka WASA কাজটি নির্ধারিত সময়ের মধ্যে (০৭/০৮/২০২৩ ইং) সিডিউল মোতাবেক শুষ্ঠভাবে সম্পন্ন করেছি।

এমতাবস্থায় আমার দাখিলকৃত আলোচ্য কাজের কার্যসমাপ্তির রিপোর্ট গ্রহন ও ১ম চলতি ও চূড়ান্ত বিল পরিশোধের ব্যবস্থা গ্রহন করতে একান্ত মর্জি হয়।

সংযুক্তঃ-

১। পেমেন্ট ইন ভয়েস।

২। কাজের তালিকা।

SAE(N)
০৭/০৮/২০২৩

AE
০৭.০৮.২৩

০৭/০৮/২৩

M/S. MITHU & BROTHERS
PROPRIETOR