

2

Office of the Executive Engineer

Store Division, Dhaka WASA


Section: 6 (Bill of Quantities with technical specification)


Name of the Work : Estimate for Site development behind of Pagla Tinshed Staff Quarters Compound under Store Division, Dhaka WASA (Lot-1).

Item No.	Group	Basis of Rate	Description of Items of Works	Unit	Qty	Unit rates or prices	Amount= (6x7)
1	2	3	4	5	6	7	8
		PWD-2022 (Revised)	Site development/Improvement by carted earth or dredged sand, sandy silt (free from any organic, foreign, environmental hazardous substances) carried by head or truck or any other means including cost of cutting or by dredging of sand, sandy silt, all; including local carrying, placing the earth/sand, sandy silt in the designated area, maintaining slopes, breaking lumps, levelling and dressing in layers up to finished level etc. all complete as per direction and accepted by the Engineer-in-charge.				
1	Civil	02.16.1	By other method/means than dredging.	cum	64	760	48640
						Total Amount=	48640

Total Amount (in word): Forty Eight Thousand Six Hundred Forty Taka Only.


MD. FAHAN ALI
Sub-Assistant Engineer
Store Division, Dhaka WASA.


PAUL SARKER
Assistant Engineer
Store Division, Dhaka WASA


মোঃ আব্দুল হান্নান
নির্বাহী প্রকৌশলী
ভান্ডার বিভাগ, ঢাকা ওয়াসা।