

Office of the Executive Engineer


Store Division, Dhaka WASA

Section: 6 (Bill of Quantities with technical specification)


Name of the Work : Estimate for Site development behind of Pagla Tinshed Staff Quarters Compound under Store Division, Dhaka WASA (Lot-2).

Item No.	Group	Basis of Rate	Description of Items of Works	Unit	Qty	Unit rates or prices	Amount= (6x7)
1	2	3	4	5	6	7	8
		PWD-2022 (Revised)	Site development/Improvement by carted earth or dredged sand, sandy silt (free from any organic, foreign, environmental hazardous substances) carried by head or truck or any other means including cost of cutting or by dredging of sand, sandy silt, all; including local carrying, placing the earth/sand, sandy silt in the designated area, maintaining slopes, breaking lumps, levelling and dressing in layers up to finished level etc. all complete as per direction and accepted by the Engineer-in-charge.				
1	Civil	02.16.1	By other method/means than dredging.	cum	65	760	49400
Total Amount=							49400

Total Amount (in word): Forty Nine Thousand Four Hundred Taka Only.


 মোঃ রাইহান আলী
 উপ-সহকারী প্রকৌশলী
 ভান্ডার বিভাগ, ঢাকা ওয়াসা।


 PAUL SARKER
 Assistant Engineer
 Store Division, Dhaka WASA


 মোঃ আব্দুল হান্নান
 নির্বাহী প্রকৌশলী
 ভান্ডার বিভাগ, ঢাকা ওয়াসা।