

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (In words) (BDT)	I have seen
1	-	N/A	"Bailing out of water caused inundation or rain dewatering arrangement at the different chambers to pump out the water deposited in the chamber and keep the chamber completely dry during cleaning work etc."	P/Day	11.000	2030.001	Two Thousand And Thirty Point Zero Zero One	22330.011	Twenty-Two Thousand Three Hundred And Thirty Point Zero One One	I have seen
2	-	N/A	"Cleaning of chambers including cleaning of any slushy materials, debris or any other foreign materials deposited in the chamber by manual labours or any other means from the bottom of chambers without making any damage to the structure and water line network and removing the sludge & debris to a safe distance place etc."	P/Chamber	6.000	3198.001	Three Thousand One Hundred And Ninety-Eight Point Zero Zero One	19188.006	Nineteen Thousand One Hundred And Eighty-Eight Point Zero Zero Six	I have seen
3	-	N/A	"Supply and application of 19 mm thick (9.5 mm X 3 2 layer) water proof, damp proof, dry and breathable plaster on roof slab/ underground water reservoir/ overhead water reservoir/ basement/retaining wall with water proof, damp proof, dry and breathable Izonil cement (STN- EN -1015-11, compressive strength 34 MPa, max depth of water penetration into hardened plaster is < 1 mm) or equivalent compound in a proportion of 1:2.4 (Izonil cement or equivalent compound 1: sand 2.4) after cement grouting on existing concrete surface including finishing the corner and edges, washing sand, cleaning the surface scaffolding and curing at least 3 days etc. all completed in all respects as per direction of Engineering-in-charge. Above mentioned plaster includes glass fiber mesh of 10 mm X 10 mm grid and weight 110 gm/sqm placed in between two layers for 08 Nos e-PRV Chamber."	Sqm	276.000	1240.001	One Thousand Two Hundred And Forty Point Zero Zero One	342240.276	Three Lakh Forty-Two Thousand Two Hundred And Forty Point Two Seven Six	I have seen
4	-	N/A	Picking up of damaged/unserviceable terraced (lime concrete) floor or roof etc. and removal of debris to a safe distance	Sqm.	275.990	65.001	Sixty-Five Point Zero Zero One	17939.625	Seventeen Thousand Nine Hundred And Thirty-Nine Point Six Two Five	I have seen
5	-	N/A	Leakage Repairing work: Including Izonil Chemical, Drill Treatment Accessories, Glass Fiber Mesh with Izonil Technician and carrying cost.	Nos	96.000	964.001	Nine Hundred And Sixty-Four Point Zero Zero One	92544.096	Ninety-Two Thousand Five Hundred And Forty-Four Point Zero Nine Six	I have seen
							Grand Total:	494242.014	Four Lakh Ninety-Four Thousand Two Hundred And Forty-Two Point Zero One Four	

L. A Marketing

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
494242.014	-5.000	469529.913	Four Lakh Sixty-Nine Thousand Five Hundred And Twenty-Nine Point Nine One Three
	Grand Total:	469529.913	Four Lakh Sixty-Nine Thousand Five Hundred And Twenty-Nine Point Nine One Three

This Tenderer's Quoted Price is Electronically Signed by Mr. Md Siddique on behalf of L. A Marketing