

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer

Civil Maintenance Division

Dhaka WASA, Dhaka

6th floor, WASA Bhaban


98 Kazi Nazrul Islam avnue, Dhaka.

Name of the Work: Repair and maintenance work of Golap-103 and kamini-301 at Duaripara steff quarter, Dhaka WASA.

Sl no	Item PWD 2022	Description of the item	Quantity	Unit	Rate	Amount
1	12.8.1	Supplying, fitting and fixing of 40mm thick Wood Plastic Composite (WPC) door shutter (minimum inner wall thickness 6mm and hinge side wall thickness 15mm) having door frame section 150mm x 62mm weighing 16.7kg/sqm with 4nos 100mm long, 3mm thick hinge, 1 no round lock, 2nos 150mm long handle, hinged cleats and carrying the same to the site and local carriage etc. All complete in all floors and accepted by the Engineer-in-charge. Door Size 6'9" x 2'6"	2.00	each	17698	35,396.00
2	26.29.1	Round headed CP Conceal Bib Cock short body (Essco/coaster/star/diamond/delux/deco/orbed/delin/triple/master/classic headed or similar head)	2	each	1,172.00	2,344.00
3	26.39.2	Moving type push shower	1	each	1,049.00	1,049.00
4	26.18.1	Supplying, fitting and fixing of best quality double bowl stainless steel sink with heavy type CI or steel brackets, 12 mm dia C.P. chain plug, 40 mm dia C.P. waste, 40 mm dia PVC waste pipe with brass coupling (750 mm length) including making hole in walls and floors and mending good the damages, finishing etc. all complete approved and accepted by the Engineer-in-charge. Approx. 1160 x 500 mm size double bowl with sink tray (Standard)	1.000	each	8,486.000	8486.00
5	1	Head mason / Mosaic head mistry	1.000	each	800.000	800.00
6	4	Ordinary labour	1.000	each	550.000	550.00
					Total TK.	48,625.00

In Word: Forty eight thousand six hundred twenty five taka Only.


০০/১/২৬
রাজিয়া সুলতানা
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াসা।


10.09.26
মুক্তান সাহা
নির্বাহী প্রকৌশলী
সিএম বিভাগ
ঢাকা ওয়াসা