

M/S. Mouno Construction

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	-	N/A	Mobilization and cleaning site before commencing actual physical work and contract during period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also cover clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge.	sqm	264.000	218.001	Two Hundred And Eighteen Point Zero Zero One	57552.264	Fifty-Seven Thousand Five Hundred And Fifty-Two Point Two Six Four	I have seen
2	-	N/A	Layout and marking for earth work in excavation in foundation accepted by the Engineer-in-charge. [Plinth area of the structure shall be considered for measurement]	sqm	264.000	19.001	Nineteen Point Zero Zero One	5016.264	Five Thousand And Sixteen Point Two Six Four	I have seen
3	-	N/A	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density 2.10.1 of 95% with optimum moisture content (Modified proctor 295.75 test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge	Cum	198.000	1088.001	One Thousand And Eighty-Eight Point Zero Zero One	215424.198	Two Lakh Fifteen Thousand Four Hundred And Twenty-Four Point One Nine Eight	I have seen
4	-	N/A	Cutting jungles and shrub including removing and cleaning the spot/site	sqm	264.000	9.001	Nine Point Zero Zero One	2376.264	Two Thousand Three Hundred And Seventy-Six Point Two Six Four	I have seen
5	-	N/A	"Carrying of rubbish, taking up all sorts of bricks, brick-bats and rubbish gravel chips, loading and 25.15 unloading at both ends including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge."	Cum	145.200	178.001	One Hundred And Seventy-Eight Point Zero Zero One	25845.745	Twenty-Five Thousand Eight Hundred And Forty-Five Point Seven Four Five	I have seen
6	-	N/A	Supply of best and approved quality alluvial loamy silty soil including loading, unloading at both ends, properly stacking] at site including supply of tools and plants etc. all complete and accepted by the Engineer-in-charge	Cum	72.730	913.001	Nine Hundred And Thirteen Point Zero Zero One	66402.562	Sixty-Six Thousand Four Hundred And Two Point Five Six Two	I have seen
7	-	N/A	Supply of well decomposed cow dung carried by trucks or any other means including loading, unloading at both ends, stacking the same at site including supply of tools and plants etc, all complete and accepted by the Engineer-in-charge	Cum	46.280	1703.001	One Thousand Seven Hundred And Three Point Zero Zero One	78814.886	Seventy-Eight Thousand Eight Hundred And Fourteen Point Eight Eight Six	I have seen
8	-	N/A	Labour charge for spreading the alluvial loamy silty soil from the stacks at site on the lawn surface, leveling, dressing the same including supply all necessary tools and plants etc. all complete and accepted by the Engineer-in-charge	Cum	72.730	194.001	One Hundred And Ninety-Four Point Zero Zero One	14109.692	Fourteen Thousand One Hundred And Nine Point Six Nine Two	I have seen
9	-	N/A	Levelling & dressing the compound or plant/flower bed as 32.73.1 per direction of Engineer-in-charge	sqm	220.000	9.001	Nine Point Zero Zero One	1980.220	One Thousand Nine Hundred And Eighty Point Two Two	I have seen

	-	N/A	Dismantling of R.C.C. beam, lintel, column, drop wall, sun shade from any height and removal of debris to a safe distance	Cum	4.000	3928.001	Three Thousand Nine Hundred And Twenty-Eight Point Zero Zero One	15712.004	Fifteen Thousand Seven Hundred And Twelve Point Zero Zero Four	I have seen
11	-	N/A	Safety measure item all complete and accepted by the Engineer-in-charge.	Item	1.000	15000.001	Fifteen Thousand Point Zero Zero One	15000.001	Fifteen Thousand Point Zero Zero One	I have seen
							Grand Total:	498234.100	Four Lakh Ninety-Eight Thousand Two Hundred And Thirty-Four Point One	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. MD. ALAM on behalf of M/S. Mouno Construction

M/S. Mouno Construction

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
498234.100	-5.000	473322.395	Four Lakh Seventy-Three Thousand Three Hundred And Twenty-Two Point Three Nine Five
	Grand Total:	473322.395	Four Lakh Seventy-Three Thousand Three Hundred And Twenty-Two Point Three Nine Five

This Tenderer's Quoted Price is Electronically Signed by Mr. MD. ALAM on behalf of M/S. Mouno Construction