

Lot Detail

Lot No. : W-9 2022-2023

Lot Preventive and post maintenance and repair work at different DMA chamber and sluice valve chamber of
Description : DMA 610,611,612 and others under MODS Zone-6. (Frame work) (Lot-4)

Bill of Quantities (BOQ)

Unit Rate Basis

Table Name : Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A		Labour for Dismantling and Earth work Excavation manhole covers. Etc	each	72	599.988	Five Hund	43199.1	Forty-Three	
2	N/A		Provide Brick soling to the base of manholes and service pits, including the supply of first class bricks, all in accordance with the Technical Specification and Standard Detail Drawings at all depths.	sqm	6.35	517.999	Five Hund	3289.29	Three Thous	
3	N/A		Erection of Brickwork (1:4) for the walls 125mm th. Of chamber at any req. depth, all in accordance with Technical Specification and direction of Engineering in charge and standard details drawings. The rate to include for the supply of first class bricks, the preparation of. Sand cement mortar including the supply of all materials and flush pointing to the face of the brickwork wall.	cum	10.79	7528.999	Seve n	81237.8	Eighty -One	
4	N/A		Placing of Mass concrete (1:3:6) for the base slab of water pipe line chamber including the supply of all materials all in accordance with Technical Specification and direction of Engineering in charge, and standard drawings.	cum	8.47	8885.999	Eight Thou	75264.4	Seven ty-	
5	N/A		Installation and laying of (uPVC) Unplasticized polyvinyl chloride/DI / PE /MS water pipelines (including supply of materials, fittings, Equipment described in schedule of requirement. 150mm dia, uPVC Pipe(C? class BS 3505)	m	31.50	804.999	Eight Hund	25357.4	Twent y-Five	
6	N/A		Bailing out all source of water from Trances channel & any other means with all leads & lifts by pump or any other means etc. all complete as per direction of the E/C.	day	16	1861.999	One Thou	29791.9	Twent y-Nine	
7	N/A		Manhole Cover fitting : Fitting of	each	22	800.999	Eight	17624.0	Seven	

		access as given below, all in accordance with the Technical Specification and the Standard Detail Drawings. The rate to include for Bitumen painting of the cover and setting in Class A Mass Concrete (with Cement) including the supply of all materials.							
8	N/A	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150mm layers including leveling, watering and compaction to achieve minimum dry density of 90% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only etc. all complete and accepted by the Engineer.	cum	2.72	1087.999	One Thou	2959.35	Two Thous	
9	N/A	Minimum 19mm thick cement Sand (F.M.,I.2) water proof, damp proof, dry and breathable plaster ('1:4)with water proof Izonil Cement (STN-EN - 1015-11 , Compressive Strength 34 MPa ,Max depth of water penetration into hardened plaster is < 1 mm) /equivalent compound to wall sudace, finishing the corner and edges including washing out sand, cleaning the surface, scaffolding and curing at least for 3 days cost of waler, electricity and other charges etc. all complete in all respect as per drawing and accepted by the Engineer -in-charge. (Izonil Cement/equivalent compound: Waler proof, damp proof dry and breathable cement).	sqm	254.30	829.999	Eight Hund	211068.	Two Lakh	
10	N/A	Safety net for manhole covers area. etc (Bamboo, rope, red cloth etc all complete)	each	18	499.999	Four Hund	8999.98	Eight Thous	
						Grand Total :	498790.		

Tenderer's Quoted Price

Table
Name : Tenderer's Quoted Price

Tenderer shall only quote the offer in percentage within the range of $\pm 5\%$ to the total estimated cost of the proposed work prepared by the PE.

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
498791.000			
Grand Total :			

M/S. Rana Enterprise

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
498791.000	-5.000	473851.450	Four Lakh Seventy-Three Thousand Eight Hundred and Fifty-One point Four Five
	Grand Total:	473851.450	Four Lakh Seventy-Three Thousand Eight Hundred and Fifty-One point Four Five

This Tenderer's Quoted Price is Electronically Signed by Mr. Md Ali Khan on behalf of M/S. Rana Enterprise