


Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.

Name of Works: Repairing Of HDPE Water Pipe Leakage & Removal dirty Water In House No. # 129 & 120/141, Block # A & C, Bashundhara DMA-801 under MODS Zone-8, Dhaka WASA.

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	110 mm dia HDPE Pipe	4.00	P/M			Supply by Sub store
2	Approved Rate	110 mm dia HDPE Sleeve E.F	6.00	Nos	2600.000	15,600.000	
3	Approved Rate	Earth work in Excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead (2*4*2.25*1.67)= 30.060cum	30.060	Cum	168.000	5,050.080	
4	Approved Rate	Repairing of water line leakage for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.(2*4*2.25*1.67)= 30.060cum)/2=15.030 cum	15.030	Cum	578.000	8,687.340	
5	Approved Rate	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutchra road surface(2*4*2.25*1.68)= 30.240cum)/2=15.120 cum	15.120	Cum	154.000	2,328.480	
6	Approved Rate	B)Removal of excavated earth/debris etc.(2*4*2.25*1.67)= 30.060cum)/2=15.030 cum	15.030	Cum	288.000	4,328.640	
7	Approved Rate	Mechanics Charge	6	P/Person	1000.000	6,000.000	
8	Approved Rate	Hire charge of de-watering pump	4	P/Day	2000.000	8,000.000	
Total Tk=						49994.540	
Say Tk.=						49995.000	

In words: Forty Nine Thousand Nine Hundred Ninety Five Taka Only.


০৫/০৯/২০২৫
মোহাম্মদ আব্দুল মতিন
সহকারী প্রকৌশলী
ডিস জোন-০৮
ঢাকা ওয়াশা।


০২.০৭.২৫
মোঃ মোস্তফা
সহকারী প্রকৌশলী
মডুস জোন-৮
ঢাকা ওয়াশা


০২/০৯/২০২৫
অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডুস জোন-৮
ঢাকা ওয়াশা।