

Office of the Executive Engineer
MODS Zone-6, Dhaka WASA

Estimate

Supply, Installation of LT-CT energy meter and display units of different DTW stations under MODS Zone-6, Dhaka WASA.

S. L. No.	Description of item	Rate Basis	Qty.	Unit	Rate (TK)	Amount (TK.)
1	2	3	4	5	6	7
	The following procurement item shall be supplied at the executive engineer office MODS Zone-6 Dhaka WASA and installation to different Pumps Station. All supplied item will be accepted to inspection by DPDC & Concern Engineer. Warranty period of all item should be 12 (Twelve) months from the date of final acceptance. If any fault will occur during warranty period tenderer/ supplier will change or repair by his own cost. All rates have VAT and related service etc.					
1	Providing and fixing 415 V , 50 Hz three phase Electronic Digital Energy Meter (KWII meter) Steel Body with glass cover on prepared board (Secure/Bemco/ Citizen/ Electro/ Heavels/ Hosaf or equivalent specification mad as per approved PDB/DPDC or similar organization.(10-10 Amps Double Tarffif).	Prev. approved rate	3	Each	69200.00	207600.00
2	Supply and fixing of 18 SWG MS Panel Board for 500 Volts. 3 Phase following busbar assembled with LT(CT) energy metering Unit,200 Amps rating 4 Nos. of bar each of minimum length 381 mm (1.5'') and cross section 150 sq.	Prev. approved rate	3	Each	18500.00	55500.00
3	DPDC Meter Test Fee, Substation (Transformer) Shut down fee and Meter exchange (Disconnection -Reconnection) charge etc.	Ass prev. DESCO/DPDC Bill	3	Each	11500.00	34500.00
4	4C X 70/35 q mm NYFGbY cable. In pucca floor/ ground/ road through 50 mm PVC Pipe having wall thickness of 2.5 mm for incoming and out going at energy meter.	PWD 27.16(b)	9	Meter	6942.00	62478.00


 কিসমত হুসেন
 কিসমত হুসেন

S. L No.	Description of item	Rate Basis	Qty.	Unit	Rtate (TK)	Amount (TK.)
1	2	3	4	5	6	7
5	Supply fitting and fixing of SS Carrage bolt for Energy Meter.	Prev. approved rate	3	Each	30.00	90.00
6	Supply fitting and fixing of preform guide grip (E-21)4	Prev. approved rate	2	Dozen	960.00	1920.00
7	Supplying Stage Tape Black/ Red/ Yellow	Prev. approved rate	2	Dozen	400.00	800.00
8	Supply fitting-fixing of Royel Bolt (14mm dia)	Prev. approved rate	15	Each	32.00	480.00
9	Supply fitting and fixing of Cable clip for incoming and outgoing at Energy Meter.	Prev. approved rate	15	Each	13.00	195.00
10	Carrying: Carrying of LT-CT Meter to DESCO/DPDC Testing Division. After test carrying to related pump stations of Dhaka WASA with proper care & arrangement	Prev. approved rate	3	per trip	5000.00	15000.00
Total TK =						378563.00
In Word : Taka Three Lac Seventy Eight Thousand Five Hundred Sixty Three Taka Only.						

সাইফুল
29/08/23
সাইফুল ইসলাম
উপ-সহকারী প্রকৌশলী
মডস জোন-৬, ঢাকা-ওয়াসা

মোঃ সাইফুল ইসলাম
সহকারী প্রকৌশলী
মডস জোন-৬, ঢাকা ওয়াসা।

মোঃ সাইফুল
29/08/23
প্রকৌঃ মোহাম্মদ মাহবুবুর রহমান
নির্বাহী প্রকৌশলী
মডস জোন-৬, ঢাকা ওয়াসা।