

Dhaka Water Supply and Sewerage Authority

Office of the Executive Engineer


Civil Maintenance Division


6th Floor, Wasa Bhaban, Kawran Bazar


98, Kazi Nazrul Islam Avenue, Dhaka-1215

Name of the Work: Construction of Ply Wood Partition Wall for the Assistant Revenue Officer's Room at Revenue Zone -01, Dhaka Wasa .

Item No.	Group	Item Code.	Description of Items of Works	Unit	Quantity	Unit rates or prices	Amount
1	Civil	18.2.1.2	Supplying, fitting and fixing 12 mm thick burma teak (BT) veneered board/ ply board/ particle board in walling with best quality and well seasoned garjan wood frame of section of 50 mm x 25 mm at 600 mm x 600 mm in grid, including grove where necessary, fitted and fixed to wall by plugs, nails, screws etc. maintaining leveled and finished exposed faces including making holes in wall and mending good the damages, if any during execution of the work, including the provisions of lighting arrangement, also including cost and carriage of all materials, electricity, accessories, labour for installation, scaffolding, screws, nails etc. all complete as per design, approved sample and accepted by the Engineer-in-charge. All sizes of wood are finished. All Garjan wood frames must be protected from termites, cockroach and other insects. Measurement will be taken as per finished surface area. The brick/ RCC surface shall be dry and damp-proof. (Rate is excluding cost of polish/ paint etc. of any type). 12 mm thick BT ply board walling	sqm	16.113	3098.001	49918.090
						Total Taka:	49,918.090
						Say Total Taka	49,918
In word: Forty Nine Thousand Nine Hundred Eighteen Taka Only.							


04.10.23
Sub-Assistant Engineer
CM Division, Dhaka WASA


8/7/26
Sub Divisional Engineer
CM Division, Dhaka WASA


04.10.23
Executive Engineer
CM Division, Dhaka WASA