

Office of the Executive Engineer

MODS Zone-9, Dhaka WASA

Name of work : Repairing of HDPE Water Line Leakage in front of house no-Ka/202/3 & removal of dirty water Khilkhet namapara road, Khilkhet railgate (DMA-909) under MODS Zone-9, Dhaka WASA.

Sl. No.	Description Of Item	Quantity	Unit	Rate (TK)	Amount (TK)
1	110 mm dia HDPE Pipe	5	P/M	2024.00	10120.00
2	110 mm dia HDPE Sleeve E.F	4	Each	2250.00	9000.00
3	Generator & Electro-Fusion Machine Hire Charge	2	P/Day	4,000.00	8,000.00
4	Mechanic Charge(For Electro-Fusion Charge)	2	P/Person	1,500.00	3,000.00
5	Service Connection	2	Each	2,020.99	4,041.98
6	Excavation (8x0.76x1.52)+{3x(1.52x1.52x1.52)}=19.78m ³	19.78	Cum	288.00	5696.64
7	Supply, depositing and compaction of fine sand (FM 0.8) bedding surrounding and above pipe(8*0.76*1.30)-1.88=6.02cum	6.02	Cum	635.00	3822.70
8	Backfilling 8x0.76x0.91+{3x(1.52x1.52x0.91)}=11.85m ³	11.85	Cum	134.00	1587.90
9	Hire Charge Of de-Watering Pump	2	P/Day	1,862.00	3,724.00
10	Bamboo, Wooden, Planked Rope, G.I Wire for temporary shoring and boxing to the side of the excavation to maintain a safe working environment for and depths.	1	L/S	1,000.00	1,000.00
Total(TK)					49,993.22

In word: Forty Nine Thousand Nine Hundred Ninety Three Point Two Two Taka Only.

Almari
31.07.2023
মোঃ মনিরুজ্জামান
উপ-সহকারী প্রকৌশলী
মডস জোন-৯, ঢাকা ওয়াসা

02/08/23
মোঃ দেলোয়ার হোসেন
সহকারী প্রকৌশলী
মডস জোন-৯
ঢাকা ওয়াসা

01.08.23
(মোঃ মোজাহিদুর রহমান)
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডস জোন-৯, ঢাকা ওয়াসা