

M/S. ZOINAL Engineering enterprise

Section 6. Bill of Quantities

Bill of Quantities

Bill of Quantities

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price (In figures: BDT)	Unit Price (In words: BDT)	Total Price (In figures: BDT)	Total Price (In words: BDT)
1	--	N/A	Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also cover clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge.	Sqm	50.000	1500.001	One Thousand Five Hundred point Zero Zero One	75000.050	Seventy-Five Thousand point Zero Five
2	--	N/A	Stripping of unserviceable plaster including racking out joints, cleaning etc (10% of Total surface).	Sqm	46.750	900.001	Nine Hundred point Zero Zero One	42075.047	Forty-Two Thousand AND Seventy-Five point Zero Four Seven
3	--	N/A	Renewing of Exterior premium acrylic emulsion paint (weather coat) of approved brand and quality	Sqm	478.800	285.001	Two Hundred and Eighty-Five point Zero Zero One	136458.479	One Lakh Thirty-Six Thousand Four Hundred and Fifty-Eight point Four Seven Nine
4	--	N/A	Renewing of Interior Premium acrylic emulsion paint (slky	Sqm	2163.260	90.001	Ninety point Zero	194695.563	One Lakh Ninety-

			finish) to walls and ceiling:2 coat.				Zero One		Four Thousand Six Hundred and Ninety-Five point Five Six Three
5	--	N/A	Renewing of premium synthetic enamel paint to door-windows frame and shutter: 2coat.	Sqm	52.985	500.001	Five Hundred point Zero Zero One	26492.553	Twenty-Six Thousand Four Hundred and Ninety-Two point Five Five Three
6	--	N/A	Renewing of painting with synthetic black enamel paint to plinth and skirting: 2coat (out side of Main Building).	Sqm	13.500	550.001	Five Hundred and Fifty point Zero Zero One	7425.014	Seven Thousand Four Hundred and Twenty-Five point Zero One Four
7	--	N/A	Supplying temporary safety measures (hessian cloth/net/Belt/ hand gloves/Sanitizer etc.) around construction work place (along the height of the building) where public safety is likely to be endangered due to construction activities; which shall be supported using scaffolding around the building for brick work/ plaster; including fitting and fixing in position providing necessary anchors, wires, ties etc. all complete and accepted by the Engineer-in-charge.	item	1.000	2000.001	Two Thousand point Zero Zero One	2000.001	Two Thousand point Zero Zero One
							Grand Total:	484146.707	Four Lakh Eighty-Four Thousand One Hundred and Forty-Six point Seven Zero Seven

* Note: All applicable taxes, custom duties, VAT and other levies payable by the Contractor under the Contract shall be included in the unit prices submitted by the Tenderer.