


Office of the Executive Engineer
MODS Zone-10, Dhaka WASA


Estimate

Name of the Work: Cleaning of 8 Nos. pump compound under MODS Zone-10, Dhaka WASA.

SL No	Item code	Description	Unit	Qty.		Amount (TK)
1	PWD 2.10.1	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge (3*.5*6=9 m3.	Cum	11	1088.00	11,968.00
2	Market rate fixed by WASA	Labor for cleaning and removing rubbish and weeds from pump compound and pump house.	Nos	28	800.00	22,400.00
3	Market rate fixed by WASA	Vehicle Rent (for remove of rabish/Garbage from pump house to farther distant/disposal point Dumping.)	P/Trip	3	5000.00	15,000.00
Total Tk=						49,368.00

In Word- Forty Nine Thousand Three Hundred Sixty Eight Taka Only.


০৬/১০/২৪
মোস্তাফিন বিল্লাহ আলমগীর
উপ-সহকারী প্রকৌশলী
মডুস জোন-১০, ঢাকা ওয়াসা।


০৬/১০/২৪
মোঃ আসাদুজ্জামান
সহকারী প্রকৌশলী
মডুস জোন-১০
ঢাকা ওয়াসা


০৬/১০/২৪
সুজন চন্দ্র বর্মণ
নির্বাহী প্রকৌশলী
মডুস জোন-১০, ঢাকা ওয়াসা।