


**OFFICE OF THE EXECUTIVE ENGINEER
MODS ZONE-10, DHAKA WASA
Estimate**


Name of the Work:-Repair works of 300 mm dia & 200 mm dia sluice valve in front of Section-11/A-1 near Monroger Hospital & in front of Bauniabad-1 Water pump under Mods Zone-10, Dhaka WASA.

SL No		Description of Materials	Unit	Quantity	Rate	Amount
1	Pre-Approved Rate	Supply of 2'-6" length 1-1/2" dia spindle for 12" dia sluice valve (as per specimen copy).	Each	1	4800.00	4800.00
2	"	Supply of 2'-0" length 1-1/4" dia spindle for 8" dia sluice valve (as per specimen copy).	Each	1	3800.00	3800.00
3	"	Repairing work of 12" dia guide nut.(Penium)	Each	1	1500.00	1500.00
4	"	Repairing work of 8" dia guide nut.(Penium)	Each	1	1000.00	1000.00
5	"	Sluice valves gate for 12" dia	Each	1	2400.00	2400.00
6	MR fixed by WASA	Labor for earth excavation to installation S/V	Nos	10	800.00	8000.00
7	pwd 02.1.2	Earthwork in excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead	cum	19.78	168.09	3324.82
8	pwd 02.10.1	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.5 to FM 0.8	cum	11.85	1088.00	12892.80
9	MR fixed by WASA	Hire Charge Of de-Watering Pump	day	2	2,000.00	4000.00
10	Wasa 1/3 b	uPVC Pipe(C' class BS 3505) 150 mm dia	Day	3	805.00	2415.00
11		Purchase for bamboo, rope, hacksaw set, GI wire etc	L.S	1	5000.00	5000.00
Total Tk. =						49,132.62

In word: Forty Nine Thousand One Hundred Thirty Two Point Six Two Only.


০৬/১০/১৮

মোস্তাফিন বিল্লাহ আলমগীর
উপ-সহকারী প্রকৌশলী
মডুস জোন-১০, ঢাকা ওয়াসা।


০৬/১০/১৮

মোঃ আসাদুজ্জামান
সহকারী প্রকৌশলী
মডুস জোন-১০
ঢাকা ওয়াসা


০৬/১০/১৮

সুজন চন্দ্র বর্মান
নির্বাহী প্রকৌশলী
মডুস জোন-১০, ঢাকা ওয়াসা।