

Office of the Executive Engineer
Savar-Keraniganj Wellfield Plant, Dhaka WASA
Bhakurta, Savar, Dhaka.
Section-6

Bill of quantity

Name of the Work: Supply, fitting & fixing of SDB at different DTW stations under SKWP.						
SL No.	Basis of rate	Description of Item	Unit	Q'ty	Unit price	Total Amount
1	PWD SoR E/M 2022 4.1.1	Providing & fixing 250V, 50 Hz grade following concealed type sub-distribution board made of 18-SWG MS sheet complete with hinged type door, built-in type locking arrangement, one no. 60 A capacity bus-bar with required no. of holes thereon on insulators at both ends, copper blocks for neutral and earth terminal, SPMCBs manufactured/assembled and tested in accordance with IEC/VDE/NEMA/BS/JIS along with relevant BDS IEC standard having minimum breaking capacity 6/10-KA with thermal over current and instantaneous electromagnetic short circuit release. necessary arrangement for fixing of MCBs duly painted with powder coating with epoxy polyester resin on all surfaces of board (gray/off-white) etc. In the front side there will be tempered thick fiberglass of minimum 8 mm thickness with rubber gaskets etc. with SPMCBs accepted/approved by the Engineer-in-charge. 3-Way SDB (with box size minimum 220mm x 132mm x 148mm) in-coming :1 x 20 amps (6 KA) & out-going: 3 x 5 / 10 amps SPMCB(6 KA).	each	12.00	4,031.000	48,372.000
Total Taka=						48,372.00
In words: Forty-Eight Thousand Three Hundred and Seventy-Two Taka Only.						

28.09
2025

মোঃ আবুল কালাম আজাদ
উপসহকারী প্রকৌশলী
সভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা

29/9/25

মোঃ সুমন আহমেদ
সহকারী প্রকৌশলী
সভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট
ঢাকা ওয়াসা।

29/09/25

মোঃ নাফিজ ইমতিয়াজ
নির্বাহী প্রকৌশলী
সভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট, ঢাকা ওয়াসা।